

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400197631

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100322

4. Contact Name: EILEEN ROBERTS

2. Name of Operator: NOBLE ENERGY INC

Phone: (303) 2284330

3. Address: 1625 BROADWAY STE 2200

Fax: (303) 2284286

City: DENVER State: CO Zip: 80202

5. API Number 05-123-32964-00

6. County: WELD

7. Well Name: WACKER B

Well Number: 10-20D

8. Location: QtrQtr: NESW Section: 10 Township: 5N Range: 64W Meridian: 6

Footage at surface: Distance: 2040 feet Direction: FSL Distance: 2421 feet Direction: FWL

As Drilled Latitude: 40.412150 As Drilled Longitude: -104.537020

GPS Data:

Data of Measurement: 03/29/2011 PDOP Reading: 2.6 GPS Instrument Operator's Name: Paul Tappy

** If directional footage at Top of Prod. Zone Dist.: 2548 feet. Direction: FSL Dist.: 1331 feet. Direction: FWL

Sec: 10 Twp: 5N Rng: 64W

** If directional footage at Bottom Hole Dist.: 2538 feet. Direction: FSL Dist.: 1335 feet. Direction: FWL

Sec: 10 Twp: 5N Rng: 64W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 03/20/2011 13. Date TD: 03/26/2011 14. Date Casing Set or D&A: 03/26/2011

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7164 TVD** 6992 17 Plug Back Total Depth MD 7082 TVD** 6910

18. Elevations GR 4604 KB 4617

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL/GRL/CCL, CDL/CNL/ML, HRIL.

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24.00	0	560	407	0	560	VISU
1ST	7+7/8	4+1/2	11.60	0	7,127	570	2,164	7,127	CBL

ADDITIONAL CEMENT

Cement work date: _____					
Details of work:					
Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
NIOBRARA	6,641		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	6,898		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	6,921		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Eileen Roberts

Title: Regulatory Specialist Date: 8/22/2011 Email: eroberts@nobleenergyinc.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400197635	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400197636	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400197631	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
Permit	hard copy logs doc#1670045-47	8/26/2011 12:56:42 PM
Permit	waiting on logs	8/22/2011 8:48:26 AM

Total: 2 comment(s)