

FORM
2Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒Refiling ☒Sidetrack ☐

Document Number:

400186493

PluggingBond SuretyID

20040071

3. Name of Operator: ANTERO RESOURCES PICEANCE CORPORATION4. COGCC Operator Number: 100795. Address: 1625 17TH ST STE 300City: DENVER State: CO Zip: 802026. Contact Name: Hannah Knopping Phone: (303)357-6412 Fax: (303)357-7315Email: hknopping@anteroresources.com7. Well Name: CSF Well Number: 33D-08-07-91

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7724

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 8 Twp: 7S Rng: 91W Meridian: 6Latitude: 39.455080 Longitude: -107.578970Footage at Surface: 211 feet FNL/FSL 2094 feet FEL/FWL FSL11. Field Name: Mamm Creek Field Number: 5250012. Ground Elevation: 6922 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 01/13/2004 PDOP Reading: 3.9 Instrument Operator's Name: David B. Dusdal15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**Footage at Top of Prod Zone: FNL/FSL 1975 FSL 1961 FEL 1975 FSL 1961 FEL 1975
Sec: 8 Twp: 7S Rng: 91W Sec: 8 Twp: 7S Rng: 91W16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 1 mi18. Distance to nearest property line: 5073 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1289 ft

20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| Iles | ILES | 191-32 | | |
| Williams Fork | WMFK | 191-32 | | |

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC 6657822. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
All of Sec 7, 8 and 9 T7S, R91W

25. Distance to Nearest Mineral Lease Line: 1975 ft 26. Total Acres in Lease: 1947

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Onsite if app(See comments)

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Btm | Cmt Top |
|-------------|--------------|----------------|--------|---------------|---------------|-----------|---------|---------|
| CONDUCTOR | 24 | 16 | 55# | 0 | 60 | 177 | 60 | 0 |
| SURF | 12+1/4 | 8+5/8 | 24/32# | 0 | 1,000 | 416 | 1,000 | 0 |
| 1ST | 7+7/8 | 4+1/2 | 11.6# | 0 | 7,724 | 825 | 7,724 | |

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments I certify that all conditions in the original permit are the same except for updated #18 and 19 distances and updated casing and cement program. There have been no changes to land use, well construction or the lease. This Refile Form 2 does not require a Form 2A because the pad has been constructed, a closed loop system is being used so no pits need to be constructed, the refilled well will not require any expansion / additional surface disturbance of the pad. The location is not in a wildlife restricted surface occupancy area (RSO); consultation with CDOW is not required and the location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii).; consultation with CDPHE is not required.#31 Mud Disposal: Antero will bury onsite if disposal meets Table 910 and if there is a provision in SUA which allows for such operation. TOP OF CEMENT OF 1ST STRING/PRODUCTION CASING WILL BE >500 FEET ABOVE TOP OF GAS.

34. Location ID: 335054

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Hannah Knopping

Title: Permit Representative Date: _____ Email: hknopping@anteroresources.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05 045 12474 00

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

| |
|--|
| |
|--|

Attachment Check List

| Att Doc Num | Name |
|-------------|------|
| | |

Total Attach: 0 Files

General Comments

User Group **Comment** **Comment Date**

| | | |
|--|--|--|
| | | |
|--|--|--|

Total: 0 comment(s)

BMP

Type **Comment**

| | |
|--|--|
| | |
|--|--|

Total: 0 comment(s)