

FORM  
17Rev  
6/99

# State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number: 2215438			

## BRADENHEAD TEST REPORT

Step 1. Record all tubing and casing pressures as found. Step 2. Sample now. If intermediate or surface casing pressure > 25 psi. In sensitive areas, 1 psi.  
Step 3. Conduct Bradenhead test. Step 4. Conduct intermediate casing test. Step 5. Send report to BLM within 3 days and to OGCC within 10 days. Include wellbore diagram if not previously submitted or if wellbore configuration has changed since prior program. Attach gas and liquid analyses if sampled.

1. OGCC Operator Number: 100264 3. BLM Lease No: \_\_\_\_\_  
 2. Name of Operator: XTO ENERGY INC  
 4. API Number: 05-067-09564-00 5. Multiple completion? ☐ Yes ☒ No  
 6. Well Name: HAMILTON Number: 2-6  
 7. Location (QtrQtr, Sec, Twp, Rng, Meridian): SESW,6,32N,6W,N  
 8. County LA PLATA 9. Field Name: IGNACIO BLANCO  
 10. Minerals: ☒ Fee ☐ State ☐ Federal ☐ Indian

11. Date of Test: 11/07/2009

12. Well Status: ☐ Flowing  
☐ Shut In ☐ Gas Lift  
☒ Pumping ☐ Injection  
☐ Clock/Intermitter  
☐ Plunger Lift

13. Number of Casing Strings:  
☒ Two ☐ Three ☐ Liner?

### 14. EXISTING PRESSURES

Record all pressures as found	Tubing: 88 Fm: _____	Tubing: _____ Fm: _____	Prod Csg 85 Fm: _____	Intermediate Csg: _____	Surf. Csg 116
-------------------------------	-------------------------	----------------------------	--------------------------	----------------------------	------------------

### BRADENHEAD TEST

Buried valve? ☐ Yes ☒ NoConfirmed open? ☒ Yes ☐ No

With gauges monitoring production, intermediate casing and tubing pressures, open surface casing (bradenhead) valve (if no intermediate casing, monitor only the production casing and tubing pressures.) Record pressures at five minute intervals Define characteristics of flow in "Bradenhead Flow" column using letter designations below:

O = No Flow; C = Continuous; D = Down to 0; V = Vapor  
 H = Water H2O; M = Mud; W = Whisper; S = Surge; G = Gas

BRADENHEAD SAMPLE TAKEN?

☒ Yes ☐ No ☒ Gas ☐ Liquid
Character of Bradenhead fluid: ☐ Clear ☐ Fresh
☐ Sulfur ☐ Salty ☐ Black

Other:(describe)

Sample cylinder number: 1235

Elapsed Time (Min:Sec)	Fm: Tubing	Fm: Tubing:	Prod Csg PSIG	Intermedia Csg PSIG	Bradenhead Flow:
00:04	88		85		W
05:00	88		85		O
10:00	88		85		O
15:00	88		86		O
20:00	88		86		O
25:00	88		86		O
30:00	89		86		O

Instantaneous Bradenhead PSIG at end of test: &gt; 0

### INTERMEDIATE CASING TEST

Buried valve? ☐ Yes ☐ NoConfirmed open? ☐ Yes ☐ No

With gauges monitoring production, intermediate casing and tubing pressures, open the intermediate casing valve. Record pressures at five minute intervals Characterize flow in "Intermediate Flow" column using letter designations below:

O = No Flow; C = Continuous; D = Down to 0; V = Vapor  
 H = Water H2O; M = Mud; W = Whisper; S = Surge; G = Gas

INTERMEDIATE SAMPLE TAKEN?

☐ Yes ☐ No ☐ Gas ☐ Liquid
Character of Intermediate fluid: ☐ Clear ☐ Fresh
☐ Sulfur ☐ Salty ☐ Black

Other:(describe)

Sample cylinder number: \_\_\_\_\_

Instantaneous Intermediate Casing PSIG at end of test: &gt;

Elapsed Time (Min:Sec)	Fm: Tubing	Fm: Tubing:	Prod Csg PSIG	Intermedia Csg PSIG	Bradenhead Flow:

Comments:

Blow BH through a 2" valve. Purge gas cylinder 10x.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Test Performed By: Leroy Sanchez Title: Lease Operator Phone: (970) 247-7708

Signed: Leroy Sanchez Title: Lease Operator Date: 11/7/2009

Witnessed By: \_\_\_\_\_ Title: \_\_\_\_\_ Agency: \_\_\_\_\_