

**FORM**  
**5**  
Rev  
02/08

**State of Colorado**  
**Oil and Gas Conservation Commission**  
1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:  
  
400199796

**DRILLING COMPLETION REPORT**

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type  Final completion  Preliminary completion

1. OGCC Operator Number: 16700 4. Contact Name: Julie Justus  
 2. Name of Operator: CHEVRON USA INC Phone: (970) 257-6042  
 3. Address: 6001 BOLLINGER CANYON RD Fax: (970) 245-6489  
 City: SAN RAMON State: CA Zip: 94583

5. API Number 05-045-17296-00 6. County: GARFIELD  
 7. Well Name: SKR Well Number: 698-09-AV-07  
 8. Location: QtrQtr: SENE Section: 9 Township: 6S Range: 98W Meridian: 6  
 Footage at surface: Distance: 1348 feet Direction: FNL Distance: 1011 feet Direction: FEL  
 As Drilled Latitude: 39.551009 As Drilled Longitude: -108.329786

GPS Data:

Date of Measurement: 12/10/2008 PDOP Reading: 3.1 GPS Instrument Operator's Name: Ivan Martin

\*\* If directional footage at Top of Prod. Zone Dist.: 1566 feet. Direction: FNL Dist.: 616 feet. Direction: FWL

Sec: 10 Twp: 6S Rng: 98W

\*\* If directional footage at Bottom Hole Dist.: 1534 feet. Direction: FNL Dist.: 608 feet. Direction: FWL

Sec: 10 Twp: 6S Rng: 98W

9. Field Name: SKINNER RIDGE 10. Field Number: 77548

11. Federal, Indian or State Lease Number: \_\_\_\_\_

12. Spud Date: (when the 1st bit hit the dirt) 05/12/2009 13. Date TD: 06/08/2009 14. Date Casing Set or D&A: 06/09/2009

15. Well Classification:

Dry  Oil  Gas/Coalbed  Disposal  Stratigraphic  Enhanced Recovery  Storage  Observation

16. Total Depth MD 6660 TVD\*\* 6194 17 Plug Back Total Depth MD 6586 TVD\*\* 6120

18. Elevations GR 5923 KB 5948

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL

20. Casing, Liner and Cement:

**CASING**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	65	0	58		0	58	CALC
SURF	12+1/4	8+5/8	24	0	948	290	0	948	CALC
1ST	7+7/8	4+1/2	11.6	0	6,660	1,065	500	6,660	CBL

### ADDITIONAL CEMENT

Cement work date: \_\_\_\_\_

Details of work:

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

21. Formation log intervals and test zones:

#### FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH G	2,234	2,363	<input type="checkbox"/>	<input type="checkbox"/>	
FORT UNION	2,363	3,516	<input type="checkbox"/>	<input type="checkbox"/>	
OHIO CREEK	3,516	3,845	<input type="checkbox"/>	<input type="checkbox"/>	
WILLIAMS FORK	3,845	6,178	<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO COAL	6,178	6,396	<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	6,396	6,552	<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Julie Justus

Title: Regulatory Specialist Date: 8/25/2011 Email: jjustus@chevron.com

#### Attachment Check List

Att Doc Num	Document Name	attached ?	
<b>Attachment Checklist</b>			
2113041	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Directional Survey **	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<b>Other Attachments</b>			
400199796	FORM 5 SUBMITTED	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400199874	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

#### General Comments

User Group	Comment	Comment Date
Permit	Rec'd cement tickets.	9/6/2011 10:20:40 AM
Permit	Waiting on Cement tickets from Opr	9/2/2011 9:07:13 AM
Permit	CBL received.	8/31/2011 7:49:22 AM

Total: 3 comment(s)