

FORM
2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400192252

PluggingBond SuretyID

20100108

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER ☐ Pilot Hole ☐
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: CARRIZO OIL & GAS INC

4. COGCC Operator Number: 10338

5. Address: 1000 LOUISIANA STREET #1500

City: HOUSTON State: TX Zip: 77002

6. Contact Name: Tina Taylor Phone: (713)328-1000 Fax: (713)358-6440

Email: tina.taylor@crzo.net

7. Well Name: WCR100 Group Well Number: 14-11-8-61

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 7199

WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 14 Twp: 8N Rng: 61W Meridian: 6

Latitude: 40.668420 Longitude: -104.180200

Footage at Surface: 272 feet FNL 460 feet FWL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 4984 13. County: WELD

14. GPS Data:

Date of Measurement: 06/02/2011 PDOP Reading: 1.7 Instrument Operator's Name: Dave Murray

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

Sec: Twp: Rng: Sec: Twp: Rng:

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 5280 ft

18. Distance to nearest property line: 300 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1250 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR		640	All

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #:

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20100170

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Township 8 North, Range 61 West, 6th P.M. Section 14 ALL

25. Distance to Nearest Mineral Lease Line: 272 ft

26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Land Farm/Evaporation

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	1,400	534	1,400	0
OPEN HOLE	8+3/4					839	7,199	5,725

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments This is a Pilot Hole for informational purposes only and will be plugged back at TD with 839 sacks of cement. Top of cement will be 5725. No conductor casing will be set.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Tina Taylor

Title: Regulatory Compliance Date: 8/4/2011 Email: tina.taylor@crzo.net

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline

Director of COGCC Date: 9/14/2011

API NUMBER

05 123 34356 00

Permit Number: _____ Expiration Date: 9/13/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us .
- 2) Plug back pilot hole as proposed on line 33 comments or at a minimum set 60 sks cement from 50' below D-Sand base to 100' above D-Sand top and set 40 sks cement 50' above Niobrara top, in addition to kick-off plug.

A well being completed deeper than 2500 feet must be 600 feet from a lease line and be at least 1200 feet from a well permitted/producing from the same formation, or requires an approved exception location. per rule 318a.

Attachment Check List

Att Doc Num	Name
2505798	SURFACE CASING CHECK
400192252	FORM 2 SUBMITTED
400192264	WELL LOCATION PLAT

Total Attach: 3 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	On hold waiting lease, orverification that this well is waiting on a spacing hearing. 9/13/2011	9/13/2011 6:11:04 AM
Permit	Waiting on October hearing.	8/30/2011 9:08:44 AM
Permit	This is a pilot/lateral drilling plan. The permits will be on hold pending the completion of the 20 day public comment period at which time they will be approved together to maintain proper API number designations.	8/5/2011 10:18:18 AM
Permit	Returned to draft. Missing answer to question #22.	3/5/2011 7:52:36 AM

Total: 4 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Material Handling and Spill Prevention	Operator will ensure 110 percent secondary containment for any volume of fluids contained at the well site during drilling and completion. Operator will implement best management practices to contain any unintentional release of fluids.
Storm Water/Erosion Control	Operator has designed the well pad with insloping and a storm water control ditch to prevent storm water run-on/runoff and the release of fluids from the location. See attached Construction Layout Drawing.
Site Specific	Fresh water for the Fresh Water Storage Pit comes from water provider; water sources permitted for consumable industrial use.
Material Handling and Spill Prevention	Operator shall not allow any fluids to flow back to the Fresh Water Storage Pit/Pond.
Site Specific	Fresh Water Storage Pit shall contain fresh water only and signage prohibiting the use of the pit for any fluid that does not come from municipal, irrigation or surface water source.
Construction	The location will be fenced and the fenced area will include the Fresh Water Storage Pit.
Pre-Construction	The COGCC to be notified 48 hours prior to construction of the Fresh Water Storage Pit.
Planning	A Form 15 Pit Report will be submitted within 30 days of construction of the fresh water storage pit.

Total: 8 comment(s)