



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199703

Date	6-10-11	Well Owner	Kerr McGee	Well No.	14-14	Lease	SWEET GRASS
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME-12)						
City, State Zip	Denver, Colorado 80202						
Type of Job			Depth	Ft. 1208			
Surface	8 7/8" CSG-24H		Bottom of Surface	Ft. 1192			
Plug			Plug Landed @	1152	Fl.	Time On	1845
Production			Pipe Landed @	1192	Fl.	Plug Down	0045
Description	Qty.	Mess.	Unit Price	Amount			
Set Up Charge	1						
Cement Neat	750	SKS					
Poz. Mix							
Calcium Chloride	2875 BBL	2.5	%				
Gel %	Fio-Cete 1/4 # Per Sack	20012090					
Mileage Charge	222	Miles					
Fuel Surcharge	222	mi/CS					
Additional Cement	40	SKS					
Mixing Rate	4 BPM	Pre-Flush	2332	-2340			
Disp. Rate	5 BPM	Mixing	2340	-0027			
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	0027	-0030			
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0030	-0045			
Water/Cement	6.25 Gal/SK						
Water Temp.	64°F						
Total Slurry Vol.	185.7	BBLS Cement					
Landed Plug @	950	PSI/Final Lift @	450	PSI			
Pre-Flush W/	30	BBLS H ₂ O	Tax Reference Code	Sub Total			
Displace W/	73.2	BBLS H ₂ O	State CO 2.9%	Tax			
Circulate	5	BBLS Cement		Total			
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		74			
1216/1217		Bulk Truck		74/74			

We do not assume any responsibility for any damage or conditions resulting from our services or pricing is subject to review and revision.

Delivered By JOE, JOSH, EVAN, ERNIE

Received By [Signature]

Customer or His Agent