

FORM
2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐

Refiling ☐
Sidetrack ☐

Document Number:

400196247

PluggingBond SuretyID

20030009

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: Justin Garrett Phone: (303)228-4449 Fax: (303)228-4286

Email: JDGarrett@nobleenergyinc.com

7. Well Name: Booth USX Well Number: EE25-12D

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 7414

WELL LOCATION INFORMATION

10. QtrQtr: SWNW Sec: 25 Twp: 7N Rng: 65W Meridian: 6

Latitude: 40.545510 Longitude: -104.616950

Footage at Surface: 2400 feet FNL/FSL 996 feet FEL/FWL
FNL FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4818 13. County: WELD

14. GPS Data:

Date of Measurement: 06/10/2011 PDOP Reading: 0.9 Instrument Operator's Name: Aaron Lund

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
2000 FSL 660 FWL 2000 FSL 660 FWL
Sec: 25 Twp: 7N Rng: 65W Sec: 25 Twp: 7N Rng: 65W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 989 ft

18. Distance to nearest property line: 996 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1085 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Codell	CODL	unspaced	80	W/2SW4
Niobrara	NBRR	unspaced	80	W/2SW4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20030012

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T7N-R65W Sec. 25: All

25. Distance to Nearest Mineral Lease Line: 660 ft

26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Closed loop

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	700	288	700	0
1ST	7+7/8	4+1/2	11.6	0	7,414	682	7,414	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor Casing will not be used. First String top of cement will be 200' above Niobrara formation. Well is part of a 7-well pad consisting of the proposed Booth EE25-01D (Doc #400196242), Booth USX EE25-02D (Doc #400196244), Booth USX EE25-03D (Doc #400196245), Booth USX EE25-11D (Doc #400196246), Booth USX EE25-12D (Doc #400196247), Booth USX EE25-15D (Doc #400196249), & Booth EE25-13D (Doc #400196248), multi-well plan attached. The production facilities for the proposed pad will be added to existing equipment 365' S of the pad site, doc #400196251. Unit Configuration = W/2SW/4. Wellhead is to be located outside of a GWA drilling window and will be located more than 50' from an existing well location. Noble requests an exception location to 318Aa, 318Ac: Exception request and waiver attached.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Justin Garrett

Title: Regulatory Specialist Date: 8/19/2011 Email: JDGarrett@nobleenergyinc.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline

Director of COGCC Date: 9/15/2011

API NUMBER

05 123 34366 00

Permit Number: _____ Expiration Date: 9/14/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 48 hour notice of MIRU to Jim Precup at 303-726-3822 or e-mail at jim.precup@state.co.us.
- 2) Comply with Rule 317.i and provide cement coverage from the end of the production casing to a minimum of 200' above the Niobrara. Verify coverage with a cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from the end of production casing to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
2481138	SURFACE CASING CHECK
400196247	FORM 2 SUBMITTED
400197814	30 DAY NOTICE LETTER
400197816	PLAT
400197817	DEVIATED DRILLING PLAN
400197818	MULTI-WELL PLAN
400197819	EXCEPTION LOC WAIVERS
400197820	EXCEPTION LOC REQUEST

Total Attach: 8 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Material Handling and Spill Prevention	Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.
Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) General Permit No. COR- 038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location, and will remain in place until the pad reaches final reclamation.
General Housekeeping	Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pickup trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.

Total: 3 comment(s)