

FORM
5

Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400200710

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type Final completion Preliminary completion

1. OGCC Operator Number: 47120
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP
3. Address: P O BOX 173779
City: DENVER State: CO Zip: 80217-
4. Contact Name: Emily Carrender
Phone: (720) 929-6282
Fax: (720) 929-7282

5. API Number 05-123-32588-00
6. County: WELD
7. Well Name: COOK Well Number: 21-9
8. Location: QtrQtr: SENW Section: 9 Township: 2N Range: 65W Meridian: 6
Footage at surface: Distance: 2374 feet Direction: FNL Distance: 2623 feet Direction: FWL
As Drilled Latitude: 40.154010 As Drilled Longitude: -104.668933

GPS Data:
Date of Measurement: 08/24/2011 PDOP Reading: 3.3 GPS Instrument Operator's Name: Renee Doiron

** If directional footage at Top of Prod. Zone Dist.: 1328 feet. Direction: FNL Dist.: 2526 feet. Direction: FEL
Sec: 9 Twp: 2N Rng: 65W
** If directional footage at Bottom Hole Dist.: 1342 feet. Direction: FNL Dist.: 2525 feet. Direction: FEL
Sec: 9 Twp: 2N Rng: 65W

9. Field Name: WATTENBERG 10. Field Number: 90750
11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 05/22/2011 13. Date TD: 05/25/2011 14. Date Casing Set or D&A: 05/26/2011

15. Well Classification:
 Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

16. Total Depth MD 7950 TVD** 7805 17 Plug Back Total Depth MD 7905 TVD** 7760

18. Elevations GR 4872 KB 4887
One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:
PRE FORM 5

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24.0	0	752	470	0	752	VISU
1ST	7+7/8	4+1/2	11.6	0	7,940	620	3,756	7,940	CALC

ADDITIONAL CEMENT

Cement work date: 05/25/2011

Details of work:

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	3,756	480	556	3,756

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	4,065		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,375	4,704	<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,038		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,300		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,320		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	7,775		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Emily Carrender

Title: Operation Specialist I Date: 8/29/2011 Email: emily.carrender@anadarko.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
400200728	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400200727	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
400200710	FORM 5 SUBMITTED	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)