



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 199612

Date <b>5-10-11</b>	Well Owner <b>Kerr McGee</b>	Well No. <b>16-14</b>	Lease <b>SWEET GRASS</b>
County <b>WELD</b>	State <b>Colorado</b>		
Charge to <b>Kerr McGee Oil &amp; Gas Onshore, LP</b>			
Address <b>1999 Broadway, Suite 3700 (XTREME-12)</b>			
City, State Zip <b>Denver, Colorado 80202</b>			
Type of Job	Depth	Fl.	
<b>Surface</b>	<b>8 5/8" CSG-24H</b>	<b>1192</b>	
Plug	Plug Landed @ <b>1147</b>	Time On <b>1100</b>	
Production	Pipe Landed @ <b>1192</b>	Plug Down <b>1430</b>	

Description			Qty.	Meas.	Unit Price	Amount	
Set Up Charge			1				
Cement Neat TYPE III			750	SKS			
Poz. Mix							
Calcium Chloride			2.5	%			
Gel % Flo-Cete 1/4 # Per Sack							
Mileage Charge			216	Miles			
Fuel Surcharge			216	MILES			
Additional Cement				SKS			
Mixing Rate	4 BPM	Pre-Flush	1320	1328			
Disp. Rate	5 BPM	Mixing	1328	1412			
Slurry Vol.	1.32³ Cu.FL/Sk	Change Valves	1412	1415			
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1415	1430			
Water/Cement		6.25 Gal/SK				20463240R	
Water Temp.		60°F				80012090	
Total Slurry Vol.		176.3 BBLS Cement					
Landed Plug @		1000 PSI/Final Lift @ 400 PSI					
Pre-Flush W/ 30		BBLS H²O	Tax Reference Code		Sub Total		
Displace W/ 72.9		BBLS H²O	State CO 2.9%		Tax		
Circulate 6		BBLS Cement	Total				
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		72			
1214/1216		Bulk Truck		72/72			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JOE, JOSH, EVAN**

Received By

Customer or His Agent