

KPK
KP Kauffman CO, INC

Supervisor	PAUL ANDERSON	Road Dir	46 at 31,.5w,.1s,.1w	Date	2/25/2011
Well	Monfort 2-30 CF&C			Elevation KB	4738
				Elevation GL	4728
Formation	Niobrara 6942-48 7040-7050. 2spf			KB Meas;	10
New perfs	6942-48. 7040-7050. 2spf 120 Deg Phase 52 holes			Cement Top	6434
Timpass	7230-35 NO NEW PERFS 2spf			Sfc Casing	8 5/8" 24# 324
				Prod Casing	4.5" 11.6# 7346
Codell	7246-7256 4spf			PBTD	7276
New perfs	7246-7256. 2spf 120 DEG Phase			TD;	7353

Frac	string		
227 jts	2 7/8 hydil n n 80 7055	capacity	40 bbls
3 jtsw	2 3/8 n 80	93 ft	0.35991 bbls
4 1/2	11.6#	98 ft	1.519 bbls
	Total		42. bbls