



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199571

Date <u>4/27/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>9-14</u>	Lease <u>Sweet Grass</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme #12)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Ft. <u>1203</u>	
<u>Surface</u> <u>8 5/8" Csg - 24"</u>	Bottom of Surface	Ft. <u>1193</u>	
Plug	Plug Landed @ <u>1149</u>	Ft.	Time On <u>1200</u>
Production	Pipe Landed @ <u>1193</u>	Ft.	Plug Down <u>1545</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>Type III</u>	750	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	216	Miles		
Fuel Surcharge	216	Miles		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	1448-	1454
Disp. Rate	5 BPM	Mixing	1454-	1527
Slurry Vol.	1.32' Cu.Ft./Sk	Change Valves	1527-	1530
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1530-	1545
Water/Cement	6.25 Gal/SK			
Water Temp.	54°F			
Total Slurry Vol.	176.3	BBLs Cement		
Landed Plug @	900	PSI/Final Lift @ 500	PSI	
Pre-Flush W/	30	BBLs H ₂ O	Tax Reference Code	Sub Total
Displace W/	73	BBLs H ₂ O	State CO 2.9%	Tax
Circulate	6	BBLs Cement	Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		72			
<u>1207/1224</u>		Bulk Truck		72/72			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Dallas & Justin

Received By

Phil

Customer or His Agent