



Petroleum Development Corporation
 Cervi 21-10
 NWNW 10 3N 63W 6 PM
 Weld County, CO
 Actual Wellbore - NOT TO SCALE!!!
 9/15/2011

KB: 4830
 GL: 4820

API#: 05-123-233701

Cement Plugs:
 Top Surface: 5 sks 15.8# G neat

Surface Casing:
8 5/8" #24 @ 628' W/ 450 sks cmt.

713'-0': 270 sks 15.8# G neat

Production Casing:
4 1/2" #10.5 @ 7556 w/ 260 sks cmt.

Top of Cement:
0' & 5800'

5634-5494: 50 sks 15.8# G neat

Cut 4 1/2" @ 5619

Perforations: none	
Old:	0
	0
	0
	0
	0
New:	0
	0
	0
	0

CIBP @ 6430 w/ 2 sks cmt

PBTD:	7554
Casing TD:	7556

NOTES

Never perforated or completed