



Petroleum Development Corporation
 Cervi 31-4
 NWNE 10 3N 63W 6 PM
 Weld County, CO
 Actual Wellbore - NOT TO SCALE!!!
 9/15/2011

KB: 4832
 GL: 4810

API#: 05-123-23368

Cement Plugs:
 Shoot sqz holes @ 700'
 pump 288 sks 15.8# G neat
 cmt to surface

Surface Casing:
8 5/8" #24 @ 592' W/ 430 sks cmt.

Production Casing:
41/2" #10.5 @ 6918 w/620 sks cmt.

Top of Cement:
0' & 800'

Perforations	
Old:	NBRR 6552-6560
	CODL 6766-6774
	0
	0
New:	0
	0
	0
	0

CIBP @ 6454 w/ 2 sks cmt

PBTD:	6886
Casing TD:	6918

NOTES

--