

**FORM
5**Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400202580

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 16700

4. Contact Name: Julie Justus

2. Name of Operator: CHEVRON USA INC

Phone: (970) 257-6042

3. Address: 6001 BOLLINGER CANYON RD

Fax: (970) 245-6489

City: SAN RAMON State: CA Zip: 94583

5. API Number 05-045-17216-00

6. County: GARFIELD

7. Well Name: SKR

Well Number: 698-04-AV-13

8. Location: QtrQtr: NESW Section: 4 Township: 6S Range: 98W Meridian: 6

Footage at surface: Distance: 1636 feet Direction: FSL Distance: 1848 feet Direction: FWL

As Drilled Latitude: 39.559217 As Drilled Longitude: -108.338394

GPS Data:

Data of Measurement: 09/30/2008 PDOP Reading: 2.9 GPS Instrument Operator's Name: Ivan Martin

** If directional footage at Top of Prod. Zone Dist.: 425 feet. Direction: FSL Dist.: 666 feet. Direction: FWL

Sec: 4 Twp: 6S Rng: 98W

** If directional footage at Bottom Hole Dist.: 379 feet. Direction: FSL Dist.: 524 feet. Direction: FWL

Sec: 4 Twp: 6S Rng: 98W

9. Field Name: SKINNER RIDGE

10. Field Number: 77548

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 12/03/2008 13. Date TD: 12/14/2008 14. Date Casing Set or D&A: 12/15/2008

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7060 TVD** 6568 17 Plug Back Total Depth MD 7033 TVD** 6524

18. Elevations GR 5959 KB 5984

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	36.95	0	58		0	58	CALC
SURF	12+1/4	8+5/8	24	0	1,310	405	0	1,325	CBL
1ST	7+7/8	4+1/2	11.6	0	7,032	1,115	500	7,060	CBL

ADDITIONAL CEMENT

Cement work date: _____

Details of work:

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH G	2,122	2,301	<input type="checkbox"/>	<input type="checkbox"/>	
FORT UNION	2,301	3,386	<input type="checkbox"/>	<input type="checkbox"/>	
OHIO CREEK	3,386	3,725	<input type="checkbox"/>	<input type="checkbox"/>	
WILLIAMS FORK	3,725	6,027	<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO COAL	6,027	6,236	<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	6,236	6,395	<input type="checkbox"/>	<input type="checkbox"/>	
COZZETTE	6,395	6,625	<input type="checkbox"/>	<input type="checkbox"/>	
CORCORAN	6,625	6,906	<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Julie Justus

Title: Regulatory Specialist Date: 9/4/2011 Email: jjustus@chevron.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400202583	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400202582	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400202580	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400202581	LAS-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
Permit	CBL BEING SCANNED.	3/9/2011 9:16:56 AM

Total: 1 comment(s)