

PICEANCE HL NAD 83

RG 14-02S-098W

Federal RG 24-14-298 Pad

Federal RG 434-14-298 - Slot A7

Federal RG 434-14-298

Plan: Plan #2 13Apr11 kjs

Standard Planning Report - Geographic

09 August, 2011

Williams
Planning Report - Geographic

Database:	Compass R5000 WIN AUTH	Local Co-ordinate Reference:	Well Federal RG 434-14-298 - Slot A7
Company:	PICEANCE HL NAD 83	TVD Reference:	KELLY BUSHING @ 6708.0usft (Frontier 10 (22' RKB) kjs)
Project:	RG 14-02S-098W	MD Reference:	KELLY BUSHING @ 6708.0usft (Frontier 10 (22' RKB) kjs)
Site:	Federal RG 24-14-298 Pad	North Reference:	True
Well:	Federal RG 434-14-298	Survey Calculation Method:	Minimum Curvature
Wellbore:	Federal RG 434-14-298		
Design:	Plan #2 13Apr11 kjs		

Project	RG 14-02S-098W, Rio Blanco County, CO, RG 14-02S-098W		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Colorado Central Zone		Using geodetic scale factor

Site	Federal RG 24-14-298 Pad		
Site Position:		Northing:	1,754,584.50 usft
From:	Map	Easting:	2,196,448.10 usft
Position Uncertainty:	0.0 usft	Slot Radius:	13.200 in
		Latitude:	39° 52' 13.383 N
		Longitude:	108° 21' 47.349 W
		Grid Convergence:	-1.806 °

Well	Federal RG 434-14-298 - Slot A7		
Well Position	+N/-S	0.0 usft	Northing:
	+E/-W	0.0 usft	Easting:
Position Uncertainty	0.0 usft		Wellhead Elevation:
			Latitude:
			Longitude:
			Ground Level:

Wellbore	Federal RG 434-14-298				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2005-10	8/30/2007	11.040	66.088	52,801

Design	Plan #2 13Apr11 kjs			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.0	0.0	0.0	69.73

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.000	
120.0	0.00	0.00	120.0	0.0	0.0	0.00	0.00	0.00	0.000	
771.9	13.04	77.10	766.3	16.5	72.0	2.00	2.00	0.00	77.096	
5,514.2	13.04	77.10	5,386.3	255.4	1,114.8	0.00	0.00	0.00	0.000	
6,383.3	0.00	0.00	6,248.0	277.4	1,210.7	1.50	-1.50	0.00	180.000	
6,483.3	0.00	0.00	6,348.0	277.4	1,210.7	0.00	0.00	0.00	0.000	Mesaverde (25' Radiu
11,143.3	0.00	0.00	11,008.0	277.4	1,210.7	0.00	0.00	0.00	0.000	

Williams
Planning Report - Geographic

Database:	Compass R5000 WIN AUTH	Local Co-ordinate Reference:	Well Federal RG 434-14-298 - Slot A7
Company:	PICEANCE HL NAD 83	TVD Reference:	KELLY BUSHING @ 6708.0usft (Frontier 10 (22' RKB) kjs)
Project:	RG 14-02S-098W	MD Reference:	KELLY BUSHING @ 6708.0usft (Frontier 10 (22' RKB) kjs)
Site:	Federal RG 24-14-298 Pad	North Reference:	True
Well:	Federal RG 434-14-298	Survey Calculation Method:	Minimum Curvature
Wellbore:	Federal RG 434-14-298		
Design:	Plan #2 13Apr11 kjs		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude	
0.0	0.00	0.00	0.0	0.0	0.0	1,754,554.60	2,196,446.80	39° 52' 13.088 N	108° 21' 47.353 W	
120.0	0.00	0.00	120.0	0.0	0.0	1,754,554.60	2,196,446.80	39° 52' 13.088 N	108° 21' 47.353 W	
Start Build 2.00										
771.9	13.04	77.10	766.3	16.5	72.0	1,754,568.81	2,196,519.26	39° 52' 13.251 N	108° 21' 46.430 W	
Hold 13.04 Inclination										
814.7	13.04	77.10	808.0	18.6	81.4	1,754,570.67	2,196,528.75	39° 52' 13.272 N	108° 21' 46.309 W	
Green River Fm										
958.4	13.04	77.10	948.0	25.9	113.0	1,754,576.92	2,196,560.56	39° 52' 13.343 N	108° 21' 45.904 W	
A Groove										
1,153.4	13.04	77.10	1,138.0	35.7	155.9	1,754,585.38	2,196,603.74	39° 52' 13.441 N	108° 21' 45.354 W	
B Groove										
1,481.9	13.04	77.10	1,458.0	52.3	228.1	1,754,599.65	2,196,676.45	39° 52' 13.604 N	108° 21' 44.428 W	
Dissolution Surface										
2,190.2	13.04	77.10	2,148.0	87.9	383.8	1,754,630.40	2,196,833.24	39° 52' 13.957 N	108° 21' 42.430 W	
Garden Gulch										
2,385.2	13.04	77.10	2,338.0	97.8	426.7	1,754,638.87	2,196,876.41	39° 52' 14.054 N	108° 21' 41.880 W	
Orange Marker										
2,595.6	13.04	77.10	2,543.0	108.4	473.0	1,754,648.01	2,196,922.99	39° 52' 14.158 N	108° 21' 41.287 W	
Wasatch										
3,365.5	13.04	77.10	3,293.0	147.1	642.3	1,754,681.44	2,197,093.41	39° 52' 14.542 N	108° 21' 39.116 W	
9 5/8"										
4,540.8	13.04	77.10	4,438.0	206.4	900.7	1,754,732.48	2,197,353.59	39° 52' 15.127 N	108° 21' 35.801 W	
G' Sand										
4,828.2	13.04	77.10	4,718.0	220.8	963.9	1,754,744.96	2,197,417.22	39° 52' 15.270 N	108° 21' 34.991 W	
Ft. Union										
5,514.2	13.04	77.10	5,386.3	255.4	1,114.8	1,754,774.75	2,197,569.08	39° 52' 15.611 N	108° 21' 33.056 W	
Start Drop -1.50										
6,233.3	2.25	77.10	6,098.0	276.7	1,207.9	1,754,793.13	2,197,662.81	39° 52' 15.822 N	108° 21' 31.862 W	
Ohio Creek										
6,383.3	0.00	0.00	6,248.0	277.4	1,210.7	1,754,793.70	2,197,665.70	39° 52' 15.829 N	108° 21' 31.825 W	
Vertical										
6,483.3	0.00	0.00	6,348.0	277.4	1,210.7	1,754,793.70	2,197,665.70	39° 52' 15.829 N	108° 21' 31.825 W	
Mesaverde - Mesaverde - Mesaverde (25' Radius) Federal RG 434-14-298										
6,843.3	0.00	0.00	6,708.0	277.4	1,210.7	1,754,793.70	2,197,665.70	39° 52' 15.829 N	108° 21' 31.825 W	
7,293.3	0.00	0.00	7,158.0	277.4	1,210.7	1,754,793.70	2,197,665.70	39° 52' 15.829 N	108° 21' 31.825 W	
Top Gas										
9,353.3	0.00	0.00	9,218.0	277.4	1,210.7	1,754,793.70	2,197,665.70	39° 52' 15.829 N	108° 21' 31.825 W	
Cameo Coals										
9,943.3	0.00	0.00	9,808.0	277.4	1,210.7	1,754,793.70	2,197,665.70	39° 52' 15.829 N	108° 21' 31.825 W	
Rollins SS										
10,078.3	0.00	0.00	9,943.0	277.4	1,210.7	1,754,793.70	2,197,665.70	39° 52' 15.829 N	108° 21' 31.825 W	
Cozzette										
10,308.3	0.00	0.00	10,173.0	277.4	1,210.7	1,754,793.70	2,197,665.70	39° 52' 15.829 N	108° 21' 31.825 W	
Corcoran										
10,653.3	0.00	0.00	10,518.0	277.4	1,210.7	1,754,793.70	2,197,665.70	39° 52' 15.829 N	108° 21' 31.825 W	
Upper Sego										
10,893.3	0.00	0.00	10,758.0	277.4	1,210.7	1,754,793.70	2,197,665.70	39° 52' 15.829 N	108° 21' 31.825 W	
Lower Sego										
11,143.3	0.00	0.00	11,008.0	277.4	1,210.7	1,754,793.70	2,197,665.70	39° 52' 15.829 N	108° 21' 31.825 W	
TD at 11143.3										

Williams
Planning Report - Geographic

Database:	Compass R5000 WIN AUTH	Local Co-ordinate Reference:	Well Federal RG 434-14-298 - Slot A7
Company:	PICEANCE HL NAD 83	TVD Reference:	KELLY BUSHING @ 6708.0usft (Frontier 10 (22' RKB) kjs)
Project:	RG 14-02S-098W	MD Reference:	KELLY BUSHING @ 6708.0usft (Frontier 10 (22' RKB) kjs)
Site:	Federal RG 24-14-298 Pad	North Reference:	True
Well:	Federal RG 434-14-298	Survey Calculation Method:	Minimum Curvature
Wellbore:	Federal RG 434-14-298		
Design:	Plan #2 13Apr11 kjs		

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
Mesaverde (25' Radius) - plan hits target center - Circle (radius 25.0)	0.00	0.00	6,348.0	277.4	1,210.7	1,754,793.70	2,197,665.70	39° 52' 15.829 N	108° 21' 31.825 W

Casing Points					
Measured Depth (usft)	Vertical Depth (usft)	Name	Casing Diameter (in)	Hole Diameter (in)	
3,365.5	3,293.0	9 5/8"	9.625	12.250	

Formations						
Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)	
814.7	808.0	Green River Fm				
958.4	948.0	A Groove				
1,153.4	1,138.0	B Groove				
1,481.9	1,458.0	Dissolution Surface				
2,190.2	2,148.0	Garden Gulch				
2,385.2	2,338.0	Orange Marker				
2,595.6	2,543.0	Wasatch				
4,540.8	4,438.0	G' Sand				
4,828.2	4,718.0	Ft. Union				
6,233.3	6,098.0	Ohio Creek				
6,483.3	6,348.0	Mesaverde				
7,293.3	7,158.0	Top Gas				
9,353.3	9,218.0	Cameo Coals				
9,943.3	9,808.0	Rollins SS				
10,078.3	9,943.0	Cozzette				
10,308.3	10,173.0	Corcoran				
10,653.3	10,518.0	Upper Sego				
10,893.3	10,758.0	Lower Sego				

Plan Annotations				
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
120.0	120.0	0.0	0.0	Start Build 2.00
771.9	766.3	16.5	72.0	Hold 13.04 Inclination
5,514.2	5,386.3	255.4	1,114.8	Start Drop -1.50
6,383.3	6,248.0	277.4	1,210.7	Vertical
6,483.3	6,348.0	277.4	1,210.7	Mesaverde
11,143.3	11,008.0	277.4	1,210.7	TD at 11143.3