

CURRENT WELLBORE DIAGRAM

Operator: Encana Oil & Gas (USA) Inc.
Well Name: SOUTH DOUGLAS CREEK 7330
Lease Number: COC03963
Unit Number: COC47687A
Location: NWNW Sec.12 - T4S - R102W
Field: Douglas Creek South
County, State: Rio Blanco, CO
API Number: 05-103-09729-0000
Diagram Date: As of 09/21/2011

KB 6555 ft.
 GL 6548 ft.

Surface csg. CMT to surface

Lead: 35 sks Class G
 Tail: 50 sks Class G

Production csg CMT to surface

First stage cement:
 150 sks 50-50 poz mix
 Second stage cement:
 100 sks Class G

CMT plug = 100' to surface
 Pumped 45 sks in csg. & ann.

CMT plug = 1353' to 920'
 Pumped 120 sks CMT

OPEN HOLE COMPLETION
 1275' - 1362'(TD)

PBTD (ft): 1353
 TD (ft): 1362

CASING RECORD

SIZE (in)	WT (lb/ft)	GRADE	Hole D(in)	TOP (ft)	BTM (ft)	Date Run
9 5/8	36	assumed J-55	12 3/4	0	94	
7	23	J-55	8 3/4	0	1,275	

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)	Date Run

JEWELRY RECORD

ITEM	MAKER	SIZE (in)	Max ID	TOP (ft)	Date Run

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	SPF	Holes	Date Shot
Castlegate	1275	1362		OPEN HOLE	

COMMENTS/HISTORY:

P&A DATE = 08/15/2011