

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number: 400200923			
PluggingBond SuretyID 20030009			

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐
Sidetrack ☐

3. Name of Operator: NOBLE ENERGY INC 4. COGCC Operator Number: 100322
5. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202
6. Contact Name: JEAN MUSE-REYNOLDS Phone: (303)228-4316 Fax: (303)228-4286
Email: jmuse@nobleenergyinc.com
7. Well Name: HYRUP Well Number: 12-42A (12Hpad)
8. Unit Name (if appl): _____ Unit Number: _____
9. Proposed Total Measured Depth: 6926

WELL LOCATION INFORMATION

10. QtrQtr: SENE Sec: 12 Twp: 8S Rng: 96W Meridian: 6
Latitude: 39.366164 Longitude: -108.051699

Footage at Surface: 2276 feet FNL/FSL 967 feet FEL/FWL FEL

11. Field Name: GRAND VALLEY Field Number: 31290

12. Ground Elevation: 6155 13. County: MESA

14. GPS Data:

Date of Measurement: 06/17/2011 PDOP Reading: 0.8 Instrument Operator's Name: RON RENNKE

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1528 FNL 622 FEL FEL Bottom Hole: FNL/FSL 1528 FNL 622 FEL FEL
Sec: 12 Twp: 8S Rng: 96W Sec: 12 Twp: 8S Rng: 96W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1124 ft

18. Distance to nearest property line: 928 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 295 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	139-45	40	1420

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

SENE Sec 12 - T8S - R96W, 6th P.M.

25. Distance to Nearest Mineral Lease Line: 928 ft

26. Total Acres in Lease: 1420

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☒ Yes ☐ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: EVAPORATE & BURY

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20+0/0	16+0/0		0	60	15	60	0
SURF	12+1/4	8+5/8	32	0	1,500	355	1,500	0
1ST	6+0/0	4+1/2	11.6	0	6,926	500	6,926	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Parasite string 3000'. The Production Casing Top of Cement will be 200' above Top of Gas.No pits will be constructed. A closed loop system will be used for this APD.This location does not require a variance from any of the rules listed in COGCC Rule 306.d (1). (A).(ii). This location is not in a wildlife restricted surface occupancy area.

34. Location ID: 312697

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JEAN MUSE-REYNOLDS

Title: REGULATORY COMPLIANCE Date: 8/31/2011 Email: jmuse@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nash

Director of COGCC Date: 9/25/2011

API NUMBER

05 077 10173 00

Permit Number: _____ Expiration Date: 9/24/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

NO PUBLIC OR DOW COMMENTS. FINAL COMPREHENSIVE REVIEW STATUS--PASSED.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 340 FEET DEEP.

Attachment Check List

Att Doc Num	Name
400200923	FORM 2 SUBMITTED
400200928	H2S CONTINGENCY PLAN
400200931	OTHER
400200933	CONST. LAYOUT DRAWINGS
400200936	ACCESS ROAD MAP
400200937	OTHER
400200938	HYDROLOGY MAP
400200939	REFERENCE AREA MAP
400200941	ACCESS ROAD MAP
400200942	LOCATION PICTURES
400200943	REFERENCE AREA PICTURES
400200944	MULTI-WELL PLAN
400200945	LOCATION DRAWING
400200946	NRCS MAP UNIT DESC
400200947	NRCS MAP UNIT DESC
400200948	OIL & GAS LEASE
400202343	WELL LOCATION PLAT
400202344	DEVIATED DRILLING PLAN

Total Attach: 18 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Req'd clarification from oper. on dist. to nearest well, dist. to nearest min. lease, unit config. Need to attach 2A	9/16/2011 3:39:15 PM
Permit	Returned to draft. Missing question #19, location ID #, mud disposal info. Attachments are for a different well.	9/1/2011 7:13:05 AM

Total: 2 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
General Housekeeping	<ul style="list-style-type: none">• Waste minimization practices including re-use and recycling when practicable.• Waste management (handling and disposal) practices in accordance with COGCC rules and RCRA guidelines as applicable.• Good housekeeping practices relative to overall site condition.
Drilling/Completion Operations	<ul style="list-style-type: none">• Spill reporting and cleanup per COGCC guidelines, EPA regulations, CDPEH regulations, and Noble Energy Inc. policies.
Planning	<ul style="list-style-type: none">• Traffic minimization practices whenever possible in order to reduce dust, noise, congestion, road maintenance.• Noise minimization.• Use of multi-well pad sites for the purpose of minimizing areas of disturbance, traffic, and environmental impact.• Proper reclamation and reseeding practices in accordance with COGCC rules, landowner requirements and BLM stipulations as applicable.
Wildlife	Bird protection practices in accordance with the Migratory Bird Act.
Material Handling and Spill Prevention	<ul style="list-style-type: none">• Spill Prevention Control and Countermeasure (SPCC) Plans in accordance with 40 CFR, Part 112.• Secondary containment for oil and produced water vessels in accordance with COGCC rules.
Interim Reclamation	Use of portable toilets whenever long-term activities are occurring onsite.
Storm Water/Erosion Control	<ul style="list-style-type: none">• Stormwater management practices during construction and interim reclamations phases in accordance with CDPHE regulations.• Stormwater management practices in accordance with COGCC rules throughout the operating life of the locations.

Total: 7 comment(s)