

PICEANCE HL NAD 83

RG 14-02S-098W

Federal RG 24-14-298 Pad

Federal RG 524-14-298 - Slot A10

Federal RG 524-14-298

Plan: Plan #2 13Apr11 kjs

Standard Planning Report - Geographic

09 August, 2011

Williams
Planning Report - Geographic

Database:	Compass R5000 WIN AUTH	Local Co-ordinate Reference:	Well Federal RG 524-14-298 - Slot A10
Company:	PICEANCE HL NAD 83	TVD Reference:	KELLY BUSHING @ 6708.0usft (Frontier 10 (22' RKB) kjs)
Project:	RG 14-02S-098W	MD Reference:	KELLY BUSHING @ 6708.0usft (Frontier 10 (22' RKB) kjs)
Site:	Federal RG 24-14-298 Pad	North Reference:	True
Well:	Federal RG 524-14-298	Survey Calculation Method:	Minimum Curvature
Wellbore:	Federal RG 524-14-298		
Design:	Plan #2 13Apr11 kjs		

Project	RG 14-02S-098W, Rio Blanco County, CO, RG 14-02S-098W		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Colorado Central Zone		Using geodetic scale factor

Site	Federal RG 24-14-298 Pad		
Site Position:		Northing:	1,754,584.50 usft
From:	Map	Easting:	2,196,448.10 usft
Position Uncertainty:	0.0 usft	Slot Radius:	13.200 in
		Latitude:	39° 52' 13.383 N
		Longitude:	108° 21' 47.349 W
		Grid Convergence:	-1.806 °

Well	Federal RG 524-14-298 - Slot A10					
Well Position	+N/-S	0.0 usft	Northing:	1,754,577.10 usft	Latitude:	39° 52' 13.310 N
	+E/-W	0.0 usft	Easting:	2,196,447.70 usft	Longitude:	108° 21' 47.351 W
Position Uncertainty		0.0 usft	Wellhead Elevation:		Ground Level:	6,686.0 usft

Wellbore	Federal RG 524-14-298				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2005-10	8/30/2007	11.040	66.088	52,802

Design	Plan #2 13Apr11 kjs			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	6,268.0	0.0	0.0	282.94

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.000	
120.0	0.00	0.00	120.0	0.0	0.0	0.00	0.00	0.00	0.000	
188.6	1.03	282.94	188.6	0.1	-0.6	1.50	1.50	0.00	282.938	
5,700.3	1.03	282.94	5,699.4	22.3	-97.1	0.00	0.00	0.00	0.000	
5,768.9	0.00	0.00	5,768.0	22.4	-97.7	1.50	-1.50	0.00	180.000	
6,268.9	0.00	0.00	6,268.0	22.4	-97.7	0.00	0.00	0.00	0.000	Mesaverde (25' Radius
10,918.9	0.00	0.00	10,918.0	22.4	-97.7	0.00	0.00	0.00	0.000	

Williams
Planning Report - Geographic

Database:	Compass R5000 WIN AUTH	Local Co-ordinate Reference:	Well Federal RG 524-14-298 - Slot A10
Company:	PICEANCE HL NAD 83	TVD Reference:	KELLY BUSHING @ 6708.0usft (Frontier 10 (22' RKB) kjs)
Project:	RG 14-02S-098W	MD Reference:	KELLY BUSHING @ 6708.0usft (Frontier 10 (22' RKB) kjs)
Site:	Federal RG 24-14-298 Pad	North Reference:	True
Well:	Federal RG 524-14-298	Survey Calculation Method:	Minimum Curvature
Wellbore:	Federal RG 524-14-298		
Design:	Plan #2 13Apr11 kjs		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude	
0.0	0.00	0.00	0.0	0.0	0.0	1,754,577.10	2,196,447.70	39° 52' 13.310 N	108° 21' 47.351 W	
120.0	0.00	0.00	120.0	0.0	0.0	1,754,577.10	2,196,447.70	39° 52' 13.310 N	108° 21' 47.351 W	
Start Build 1.50										
188.6	1.03	282.94	188.6	0.1	-0.6	1,754,577.26	2,196,447.10	39° 52' 13.311 N	108° 21' 47.359 W	
Hold 1.03 Inclination										
818.1	1.03	282.94	818.0	2.7	-11.6	1,754,580.13	2,196,436.17	39° 52' 13.336 N	108° 21' 47.500 W	
Green River Fm										
953.1	1.03	282.94	953.0	3.2	-14.0	1,754,580.75	2,196,433.83	39° 52' 13.342 N	108° 21' 47.530 W	
A Groove										
1,143.2	1.03	282.94	1,143.0	4.0	-17.3	1,754,581.62	2,196,430.53	39° 52' 13.349 N	108° 21' 47.573 W	
B Groove										
1,458.2	1.03	282.94	1,458.0	5.2	-22.8	1,754,583.06	2,196,425.06	39° 52' 13.362 N	108° 21' 47.644 W	
Dissolution Surface										
2,128.3	1.03	282.94	2,128.0	7.9	-34.5	1,754,586.12	2,196,413.42	39° 52' 13.389 N	108° 21' 47.794 W	
Garden Gulch										
2,318.3	1.03	282.94	2,318.0	8.7	-37.9	1,754,586.99	2,196,410.12	39° 52' 13.396 N	108° 21' 47.837 W	
Orange Marker										
2,528.4	1.03	282.94	2,528.0	9.5	-41.5	1,754,587.95	2,196,406.47	39° 52' 13.404 N	108° 21' 47.884 W	
Wasatch										
3,278.5	1.03	282.94	3,278.0	12.6	-54.7	1,754,591.38	2,196,393.45	39° 52' 13.434 N	108° 21' 48.052 W	
9 5/8"										
4,403.7	1.03	282.94	4,403.0	17.1	-74.4	1,754,596.52	2,196,373.91	39° 52' 13.479 N	108° 21' 48.305 W	
G' Sand										
4,678.7	1.03	282.94	4,678.0	18.2	-79.2	1,754,597.77	2,196,369.13	39° 52' 13.490 N	108° 21' 48.366 W	
Ft. Union										
5,700.3	1.03	282.94	5,699.4	22.3	-97.1	1,754,602.44	2,196,351.39	39° 52' 13.530 N	108° 21' 48.596 W	
Start Drop -1.50										
5,768.9	0.00	0.00	5,768.0	22.4	-97.7	1,754,602.60	2,196,350.80	39° 52' 13.532 N	108° 21' 48.603 W	
Vertical										
6,008.9	0.00	0.00	6,008.0	22.4	-97.7	1,754,602.60	2,196,350.80	39° 52' 13.532 N	108° 21' 48.603 W	
Ohio Creek										
6,268.9	0.00	0.00	6,268.0	22.4	-97.7	1,754,602.60	2,196,350.80	39° 52' 13.532 N	108° 21' 48.603 W	
Mesaverde - Mesaverde - Mesaverde (25' Radius) Federal RG 524-14-298										
7,158.9	0.00	0.00	7,158.0	22.4	-97.7	1,754,602.60	2,196,350.80	39° 52' 13.532 N	108° 21' 48.603 W	
Top Gas										
9,108.9	0.00	0.00	9,108.0	22.4	-97.7	1,754,602.60	2,196,350.80	39° 52' 13.532 N	108° 21' 48.603 W	
Cameo Coals										
9,708.9	0.00	0.00	9,708.0	22.4	-97.7	1,754,602.60	2,196,350.80	39° 52' 13.532 N	108° 21' 48.603 W	
Rollins SS										
9,833.9	0.00	0.00	9,833.0	22.4	-97.7	1,754,602.60	2,196,350.80	39° 52' 13.532 N	108° 21' 48.603 W	
Cozzette										
10,063.9	0.00	0.00	10,063.0	22.4	-97.7	1,754,602.60	2,196,350.80	39° 52' 13.532 N	108° 21' 48.603 W	
Corcoran										
10,433.9	0.00	0.00	10,433.0	22.4	-97.7	1,754,602.60	2,196,350.80	39° 52' 13.532 N	108° 21' 48.603 W	
Upper Sego										
10,668.9	0.00	0.00	10,668.0	22.4	-97.7	1,754,602.60	2,196,350.80	39° 52' 13.532 N	108° 21' 48.603 W	
Lower Sego										
10,918.9	0.00	0.00	10,918.0	22.4	-97.7	1,754,602.60	2,196,350.80	39° 52' 13.532 N	108° 21' 48.603 W	
TD at 10918.9 - TD										

Williams
Planning Report - Geographic

Database:	Compass R5000 WIN AUTH	Local Co-ordinate Reference:	Well Federal RG 524-14-298 - Slot A10
Company:	PICEANCE HL NAD 83	TVD Reference:	KELLY BUSHING @ 6708.0usft (Frontier 10 (22' RKB) kjs)
Project:	RG 14-02S-098W	MD Reference:	KELLY BUSHING @ 6708.0usft (Frontier 10 (22' RKB) kjs)
Site:	Federal RG 24-14-298 Pad	North Reference:	True
Well:	Federal RG 524-14-298	Survey Calculation Method:	Minimum Curvature
Wellbore:	Federal RG 524-14-298		
Design:	Plan #2 13Apr11 kjs		

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
Mesaverde (25' Radius) - plan hits target center - Circle (radius 25.0)	0.00	0.00	6,268.0	22.4	-97.7	1,754,602.60	2,196,350.80	39° 52' 13.532 N	108° 21' 48.603 W

Casing Points					
Measured Depth (usft)	Vertical Depth (usft)	Name	Casing Diameter (in)	Hole Diameter (in)	
3,278.5	3,278.0	9 5/8"	9.625	12.250	

Formations						
Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)	
818.1	818.0	Green River Fm				
953.1	953.0	A Groove				
1,143.2	1,143.0	B Groove				
1,458.2	1,458.0	Dissolution Surface				
2,128.3	2,128.0	Garden Gulch				
2,318.3	2,318.0	Orange Marker				
2,528.4	2,528.0	Wasatch				
4,403.7	4,403.0	G' Sand				
4,678.7	4,678.0	Ft. Union				
6,008.9	6,008.0	Ohio Creek				
6,268.9	6,268.0	Mesaverde				
7,158.9	7,158.0	Top Gas				
9,108.9	9,108.0	Cameo Coals				
9,708.9	9,708.0	Rollins SS				
9,833.9	9,833.0	Cozzette				
10,063.9	10,063.0	Corcoran				
10,433.9	10,433.0	Upper Sego				
10,668.9	10,668.0	Lower Sego				
10,918.9	10,918.0	TD				

Plan Annotations					
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates			
		+N/-S (usft)	+E/-W (usft)	Comment	
120.0	120.0	0.0	0.0	Start Build 1.50	
188.6	188.6	0.1	-0.6	Hold 1.03 Inclination	
5,700.3	5,699.4	22.3	-97.1	Start Drop -1.50	
5,768.9	5,768.0	22.4	-97.7	Vertical	
6,268.9	6,268.0	22.4	-97.7	Mesaverde	
10,918.9	10,918.0	22.4	-97.7	TD at 10918.9	