

# **PICEANCE HL NAD 83**

**RG 14-02S-098W**

**Federal RG 24-14-298 Pad**

**Federal RG 414-14-298 - Slot B11**

**Federal RG 414-14-298**

**Plan: Plan #2 13Apr11 kjs**

## **Standard Planning Report - Geographic**

**09 August, 2011**

**Williams**  
Planning Report - Geographic

<b>Database:</b>	Compass R5000 WIN AUTH	<b>Local Co-ordinate Reference:</b>	Well Federal RG 414-14-298 - Slot B11
<b>Company:</b>	PICEANCE HL NAD 83	<b>TVD Reference:</b>	KELLY BUSHING @ 6708.0usft (Frontier 10 (22' RKB) kjs)
<b>Project:</b>	RG 14-02S-098W	<b>MD Reference:</b>	KELLY BUSHING @ 6708.0usft (Frontier 10 (22' RKB) kjs)
<b>Site:</b>	Federal RG 24-14-298 Pad	<b>North Reference:</b>	True
<b>Well:</b>	Federal RG 414-14-298	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Federal RG 414-14-298		
<b>Design:</b>	Plan #2 13Apr11 kjs		

<b>Project</b>	RG 14-02S-098W, Rio Blanco County, CO, RG 14-02S-098W		
<b>Map System:</b>	US State Plane 1983	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	North American Datum 1983		
<b>Map Zone:</b>	Colorado Central Zone		Using geodetic scale factor

<b>Site</b>	Federal RG 24-14-298 Pad		
<b>Site Position:</b>		<b>Northing:</b>	1,754,584.50 usft
<b>From:</b>	Map	<b>Easting:</b>	2,196,448.10 usft
<b>Position Uncertainty:</b>	0.0 usft	<b>Slot Radius:</b>	13.200 in
		<b>Latitude:</b>	39° 52' 13.383 N
		<b>Longitude:</b>	108° 21' 47.349 W
		<b>Grid Convergence:</b>	-1.806 °

<b>Well</b>	Federal RG 414-14-298 - Slot B11		
<b>Well Position</b>	<b>+N/-S</b>	0.0 usft	<b>Northing:</b> 1,754,585.00 usft
	<b>+E/-W</b>	0.0 usft	<b>Easting:</b> 2,196,438.10 usft
<b>Position Uncertainty</b>	0.0 usft	<b>Wellhead Elevation:</b>	<b>Latitude:</b> 39° 52' 13.385 N
			<b>Longitude:</b> 108° 21' 47.477 W
			<b>Ground Level:</b> 6,686.0 usft

<b>Wellbore</b>	Federal RG 414-14-298				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Field Strength (nT)</b>
	IGRF2005-10	8/30/2007	11.040	66.088	52,802

<b>Design</b>	Plan #2 13Apr11 kjs			
<b>Audit Notes:</b>				
<b>Version:</b>	<b>Phase:</b>	PLAN	<b>Tie On Depth:</b>	0.0
<b>Vertical Section:</b>	<b>Depth From (TVD) (usft)</b>	<b>+N/-S (usft)</b>	<b>+E/-W (usft)</b>	<b>Direction (°)</b>
	0.0	0.0	0.0	277.34

<b>Plan Sections</b>										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.000	
120.0	0.00	0.00	120.0	0.0	0.0	0.00	0.00	0.00	0.000	
855.9	14.72	274.46	847.8	7.3	-93.7	2.00	2.00	0.00	274.464	
5,301.5	14.72	274.46	5,147.6	95.2	-1,219.7	0.00	0.00	0.00	0.000	
6,282.7	0.00	0.00	6,118.0	105.0	-1,344.6	1.50	-1.50	0.00	180.000	
6,382.7	0.00	0.00	6,218.0	105.0	-1,344.6	0.00	0.00	0.00	0.000	Mesaverde (25' Radius
11,002.7	0.00	0.00	10,838.0	105.0	-1,344.6	0.00	0.00	0.00	0.000	

**Williams**  
Planning Report - Geographic

<b>Database:</b>	Compass R5000 WIN AUTH	<b>Local Co-ordinate Reference:</b>	Well Federal RG 414-14-298 - Slot B11
<b>Company:</b>	PICEANCE HL NAD 83	<b>TVD Reference:</b>	KELLY BUSHING @ 6708.0usft (Frontier 10 (22' RKB) kjs)
<b>Project:</b>	RG 14-02S-098W	<b>MD Reference:</b>	KELLY BUSHING @ 6708.0usft (Frontier 10 (22' RKB) kjs)
<b>Site:</b>	Federal RG 24-14-298 Pad	<b>North Reference:</b>	True
<b>Well:</b>	Federal RG 414-14-298	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Federal RG 414-14-298		
<b>Design:</b>	Plan #2 13Apr11 kjs		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude	
0.0	0.00	0.00	0.0	0.0	0.0	1,754,585.00	2,196,438.10	39° 52' 13.385 N	108° 21' 47.477 W	
120.0	0.00	0.00	120.0	0.0	0.0	1,754,585.00	2,196,438.10	39° 52' 13.385 N	108° 21' 47.477 W	
Start Build 2.00										
814.8	13.90	274.46	808.0	6.5	-83.6	1,754,594.16	2,196,354.76	39° 52' 13.450 N	108° 21' 48.549 W	
Green River Fm										
855.9	14.72	274.46	847.8	7.3	-93.7	1,754,595.26	2,196,344.67	39° 52' 13.457 N	108° 21' 48.679 W	
Hold 14.72 Inclination										
964.6	14.72	274.46	953.0	9.5	-121.3	1,754,598.28	2,196,317.20	39° 52' 13.479 N	108° 21' 49.032 W	
A Groove										
1,166.2	14.72	274.46	1,148.0	13.5	-172.3	1,754,603.88	2,196,266.28	39° 52' 13.518 N	108° 21' 49.687 W	
B Groove										
1,486.8	14.72	274.46	1,458.0	19.8	-253.5	1,754,612.77	2,196,185.34	39° 52' 13.581 N	108° 21' 50.728 W	
Dissolution Surface										
2,174.3	14.72	274.46	2,123.0	33.4	-427.6	1,754,631.85	2,196,011.71	39° 52' 13.715 N	108° 21' 52.962 W	
Garden Gulch										
2,375.9	14.72	274.46	2,318.0	37.4	-478.7	1,754,637.44	2,195,960.79	39° 52' 13.754 N	108° 21' 53.617 W	
Orange Marker										
2,593.1	14.72	274.46	2,528.0	41.7	-533.7	1,754,643.46	2,195,905.96	39° 52' 13.797 N	108° 21' 54.322 W	
Wasatch										
3,368.5	14.72	274.46	3,278.0	57.0	-730.1	1,754,664.98	2,195,710.13	39° 52' 13.948 N	108° 21' 56.841 W	
9 5/8"										
4,490.3	14.72	274.46	4,363.0	79.2	-1,014.2	1,754,696.10	2,195,426.84	39° 52' 14.167 N	108° 22' 0.485 W	
G' Sand										
4,764.3	14.72	274.46	4,628.0	84.6	-1,083.6	1,754,703.71	2,195,357.64	39° 52' 14.221 N	108° 22' 1.375 W	
Ft. Union										
5,301.5	14.72	274.46	5,147.6	95.2	-1,219.7	1,754,718.61	2,195,221.97	39° 52' 14.326 N	108° 22' 3.120 W	
Start Drop -1.50										
6,122.6	2.40	274.46	5,958.0	104.7	-1,341.3	1,754,731.93	2,195,100.73	39° 52' 14.420 N	108° 22' 4.680 W	
Ohio Creek										
6,282.7	0.00	0.00	6,118.0	105.0	-1,344.6	1,754,732.30	2,195,097.40	39° 52' 14.422 N	108° 22' 4.723 W	
Vertical										
6,382.7	0.00	0.00	6,218.0	105.0	-1,344.6	1,754,732.30	2,195,097.40	39° 52' 14.422 N	108° 22' 4.723 W	
Mesaverde - Mesaverde - Mesaverde (25' Radius) Federal RG 414-14-298										
7,222.7	0.00	0.00	7,058.0	105.0	-1,344.6	1,754,732.30	2,195,097.40	39° 52' 14.422 N	108° 22' 4.723 W	
Top Gas										
9,232.7	0.00	0.00	9,068.0	105.0	-1,344.6	1,754,732.30	2,195,097.40	39° 52' 14.422 N	108° 22' 4.723 W	
Cameo Coals										
9,822.7	0.00	0.00	9,658.0	105.0	-1,344.6	1,754,732.30	2,195,097.40	39° 52' 14.422 N	108° 22' 4.723 W	
Rollins SS										
9,947.7	0.00	0.00	9,783.0	105.0	-1,344.6	1,754,732.30	2,195,097.40	39° 52' 14.422 N	108° 22' 4.723 W	
Cozzette										
10,167.7	0.00	0.00	10,003.0	105.0	-1,344.6	1,754,732.30	2,195,097.40	39° 52' 14.422 N	108° 22' 4.723 W	
Corcoran										
10,512.7	0.00	0.00	10,348.0	105.0	-1,344.6	1,754,732.30	2,195,097.40	39° 52' 14.422 N	108° 22' 4.723 W	
Upper Sego										
10,752.7	0.00	0.00	10,588.0	105.0	-1,344.6	1,754,732.30	2,195,097.40	39° 52' 14.422 N	108° 22' 4.723 W	
Lower Sego										
11,002.7	0.00	0.00	10,838.0	105.0	-1,344.6	1,754,732.30	2,195,097.40	39° 52' 14.422 N	108° 22' 4.723 W	
TD at 11002.7 - TD										

**Williams**  
Planning Report - Geographic

<b>Database:</b>	Compass R5000 WIN AUTH	<b>Local Co-ordinate Reference:</b>	Well Federal RG 414-14-298 - Slot B11
<b>Company:</b>	PICEANCE HL NAD 83	<b>TVD Reference:</b>	KELLY BUSHING @ 6708.0usft (Frontier 10 (22' RKB) kjs)
<b>Project:</b>	RG 14-02S-098W	<b>MD Reference:</b>	KELLY BUSHING @ 6708.0usft (Frontier 10 (22' RKB) kjs)
<b>Site:</b>	Federal RG 24-14-298 Pad	<b>North Reference:</b>	True
<b>Well:</b>	Federal RG 414-14-298	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Federal RG 414-14-298		
<b>Design:</b>	Plan #2 13Apr11 kjs		

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
Mesaverde (25' Radius) - plan hits target center - Circle (radius 25.0)	0.00	0.00	6,218.0	105.0	-1,344.6	1,754,732.30	2,195,097.40	39° 52' 14.422 N	108° 22' 4.723 W

Casing Points					
Measured Depth (usft)	Vertical Depth (usft)	Name	Casing Diameter (in)	Hole Diameter (in)	
3,368.5	3,278.0	9 5/8"	9.625	12.250	

Formations						
Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)	
814.8	808.0	Green River Fm				
964.6	953.0	A Groove				
1,166.2	1,148.0	B Groove				
1,486.8	1,458.0	Dissolution Surface				
2,174.3	2,123.0	Garden Gulch				
2,375.9	2,318.0	Orange Marker				
2,593.1	2,528.0	Wasatch				
4,490.3	4,363.0	G' Sand				
4,764.3	4,628.0	Ft. Union				
6,122.6	5,958.0	Ohio Creek				
6,382.7	6,218.0	Mesaverde				
7,222.7	7,058.0	Top Gas				
9,232.7	9,068.0	Cameo Coals				
9,822.7	9,658.0	Rollins SS				
9,947.7	9,783.0	Cozzette				
10,167.7	10,003.0	Corcoran				
10,512.7	10,348.0	Upper Sego				
10,752.7	10,588.0	Lower Sego				
11,002.7	10,838.0	TD				

Plan Annotations				
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
120.0	120.0	0.0	0.0	Start Build 2.00
855.9	847.8	7.3	-93.7	Hold 14.72 Inclination
5,301.5	5,147.6	95.2	-1,219.7	Start Drop -1.50
6,282.7	6,118.0	105.0	-1,344.6	Vertical
6,382.7	6,218.0	105.0	-1,344.6	Mesaverde
11,002.7	10,838.0	105.0	-1,344.6	TD at 11002.7