

FORM
2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refilling ☐

Sidetrack ☐

Document Number:

400205885

PluggingBond SuretyID

20100017

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: JENNIFER LIND Phone: (720)876-5890 Fax: (720)876-6890

Email: JENNIFER.LIND@ENCANA.COM

7. Well Name: MELBON RANCH Well Number: 4-6-17

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7997

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 17 Twp: 2N Rng: 65W Meridian: 6

Latitude: 40.132010 Longitude: -104.688130

Footage at Surface: 209 feet FNL/FSL 2595 feet FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4918 13. County: WELD

14. GPS Data:

Date of Measurement: 08/20/2011 PDOP Reading: 1.6 Instrument Operator's Name: BURKE

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1350 FSL 2590 FEL/FWL FWL Bottom Hole: FNL/FSL 1350 FSL 2590 FEL/FWL FWL
Sec: 17 Twp: 2N Rng: 65W Sec: 17 Twp: 2N Rng: 65W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 194 ft

18. Distance to nearest property line: 60 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1110 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407	320	S/2
J SAND	JSND	232	320	S/2
NIOBRARA	NBRR	407	320	S/2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

☒

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes ☐ No ☐

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T2N-R65W-SEC.17: N/2NE, S/2

25. Distance to Nearest Mineral Lease Line: 1290 ft 26. Total Acres in Lease: 400

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	860	255	860	0
1ST	7+7/8	4+1/2	11.6	0	7,997	170	7,997	6,937
			Stage Tool		4,901	83	4,901	4,301

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE UTILIZED. ENCANA REQUESTS THE APPROVAL OF THE OMISSION OF OPEN HOLE LOGS ON THIS WELL. REQUEST LETTER ATTACHED. ENCANA ALSO REQUESTS THE APPROVAL OF RULE 318A.a AND RULE 603.a EXCEPTION LOCATION. WELLHEAD TO BE LOCATED OUTSIDE OF GWA DRILLING WINDOW AND CLOSER THAN 150' TO A PROPERTY LINE. WAIVERS ARE ATTACHED.

34. Location ID: 410171

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JENNIFER LIND

Title: REGULATORY ANALYST Date: _____ Email: JENNIFER.LIND@ENCANA.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

--

Attachment Check List

Att Doc Num	Name
400208489	TOPO MAP
400208490	OTHER
400208491	30 DAY NOTICE LETTER
400208493	WELL LOCATION PLAT
400208494	DEVIATED DRILLING PLAN
400208495	EXCEPTION LOC WAIVERS
400208499	EXCEPTION LOC REQUEST
400208500	MINERAL LEASE MAP
400208507	PROPOSED SPACING UNIT

Total Attach: 9 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)