

FORM
2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400208997

PluggingBond SuretyID

20100017

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☐ COALBED ☐ OTHER Injection Well
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Julia Carter Phone: (720)876.5240 Fax: (720)876.6240

Email: Julia.Carter@encana.com

7. Well Name: SG Well Number: WD14C-19 C19495

8. Unit Name (if appl): Story Gulch Unit Number: COC69333X

9. Proposed Total Measured Depth: 9871

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 19 Twp: 4S Rng: 95W Meridian: 6

Latitude: 39.693125 Longitude: -108.098753

Footage at Surface: 747 feet FNL/FSL 2508 feet FEL/FWL FNL FWL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 8122 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 06/21/2010 PDOP Reading: 1.2 Instrument Operator's Name: Greg Olsen

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 625 FSL 1686 FWL 625 FSL 1686 FWL
Bottom Hole: FNL/FSL 625 FSL 1686 FWL
Sec: 19 Twp: 4S Rng: 95W Sec: 19 Twp: 4S Rng: 95W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 2125 ft

18. Distance to nearest property line: 747 19. Distance to nearest well permitted/completed in the same formation(BHL): 1347 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Wasatch	WSTC			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC64805

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T4S, R95W, Sec 19: All, Sec 20: W2, Sec 28: N2, N2SW4, Sec 29: N2, Sec 30: NE4

25. Distance to Nearest Mineral Lease Line: 625 ft 26. Total Acres in Lease: 1842

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Recycle & Bury

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	20	Line Pipe	0	120		120	
SURF	14+3/4	9+5/8	36#	0	3,000	939	3,000	
1ST	8+3/4	5+1/2	17#	0	9,871	1,181	9,871	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Please note Encana Oil & Gas (USA) Inc. owns the surface. This well is designed to be used as an injection well. #17 is measured from the nearest public road. Surface casing hole size will be 14-3/4", 12-1/4" or 13-1/2". Conductor and surface casing will be run to surface. Production casing will be run 200' into surface.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Julia M. Carter

Title: Regulatory Analyst Date: 9/27/2011 Email: Julia.Carter@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400208997	FORM 2 SUBMITTED
400209007	WELL LOCATION PLAT
400209008	DEVIATED DRILLING PLAN
400209009	TOPO MAP

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)