

FORM
2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400208888

PluggingBond SuretyID

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: WEXPRO COMPANY

4. COGCC Operator Number: 95960

5. Address: P O BOX 45003

City: SALT LAKE CITY State: UT Zip: 84145-0601

6. Contact Name: Tammy Fredrickson Phone: (307)3527514 Fax: (307)3527575

Email: Tammy.Fredrickson@Questar.com

7. Well Name: BW Musser Well Number: 49

8. Unit Name (if appl): Powder Wash Unit Number: COC047671
A

9. Proposed Total Measured Depth: 9306

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 9 Twp: 11N Rng: 97W Meridian: 6

Latitude: 40.933475 Longitude: -108.298700

Footage at Surface: 567 feet FNL/FSL 2045 feet FEL/FWL
FNL FWL

11. Field Name: Powder Wash Field Number: 69800

12. Ground Elevation: 6700 13. County: MOFFAT

14. GPS Data:

Date of Measurement: 08/30/2010 PDOP Reading: 1.1 Instrument Operator's Name: D. Kay

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FNL/FWL
555 FNL 2238 FEL 555 FNL 2238 FEL
Sec: 9 Twp: 11N Rng: 97W Sec: 9 Twp: 11N Rng: 97W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 669 ft

18. Distance to nearest property line: 16191 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1200 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Fort Union	FTUN			
Wasatch	WSTC			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COD
0038749B

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

See Attached Map

25. Distance to Nearest Mineral Lease Line: 555 ft 26. Total Acres in Lease: 1895

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Closed Loop System

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20+0/0	16+0/0	42	0	80	155	80	0
SURF	12+3/4	9+5/8	36	0	1,500	834	1,500	0
1ST	7+7/8	4+1/2	13.5	0	9,306	1,336	9,306	0

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments This well will be directionally drilled and there will be four additional well bores located on the pad to minimize surface disturbance. This pad is covered under the BW Musser 41 Pad Surface Use Plan dated 09/08/2011.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jimmy Druce

Title: Operations Manager Date: _____ Email: Tammy.Fredrickson@Questar.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400208900	DEVIATED DRILLING PLAN
400208901	DRILLING PLAN
400208902	FED. DRILLING PERMIT
400208903	PLAT
400208904	TOPO MAP
400208905	ACCESS ROAD MAP
400209048	LEASE MAP

Total Attach: 7 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Construction	Storm water and erosion control methods will be utilized from the start of construction until stabilization of the site.
Drilling/Completion Operations	The location will be bermed in all areas where a fill slope is present to contain all fluids on the location.
Structural Practices	The tanks will be surrounded by a containment that is capable of containing 110% of the largest tank during the production phase of the well pad.

Total: 3 comment(s)