

WELLBORE DIAGRAM
High Sierra Water Svc
SWD C8A

NESE, Sec. 29, T11N, R62W
Weld County , CO
05-123-32858

CORRELATED TO SUPERIOR WS CCL 5/31/11

WCRs 77 at 124, .5 N, W side

10/4/2011

CLD

K.B.= 5196
G.L.= 5176
20

TOPS

Grnhn - 7524'
J Silt - 7796'
J Sand - 7822'

9-5/8", 26# K-55 LT&C CSG Set @ 1241' (12-1/4" O.H.)
Cmt'd w/ 455 sx to Surface

7" Arrowset 1 pkr set at 8962', 9/23/11 on 286 jts 2-7/8" N-80 tubing (temporary)

7", 23# N-80 LT&C CSG Set @ 9044' (8-3/4" O.H.)
Cmt'd w/ 1110 sx
TOL @ 8984' (bumper top)
#7 CP @ 8996'

Lyons - 9000'

#6 CP @ 9200'
Blank Pipe

L. Satanka- 9204'

#5 CP @ 9330'

Wolfcamp- 9328'

#4 CP @ 9422'

Amazon - 9428'
Ccl Grove-9505'

#3 CP @ 9613'

Admire - 9602'
Virgil - 9746'
Missouri - 9990' to

#2 CP @ 10070'

Lower Missouri

#1 CP @ 10213'

DesMoines - 10200'

Atokan - 10386'

4-1/2" 11.6# P-110 LT&C Slotted LNR (TOL @ 8984', EOL @ 10,556') (6-1/8" OH)
LTD=10552'
DTD=10557'

TD=10,557'

CP = Center of Packer (adjusted per Superior WS GR/CCL, 5/31/11)