



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600095

Date	7-26-11	Well Owner	Kerr McGee	Well No.	25-6	Lease	LEE
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME #15)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Ft.	845		
Surface	8 5/8" CSG-24H	Bottom of Surface		Ft.	836		
Plug		Plug Landed @	792	FL	Time On	0200	
Production		Pipe Landed @	836	FL	Plug Down	0615	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	530	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	2049652. DRL	126	Miles	
Fuel Surcharge	80012090	126	MILES	
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	0525	0530
Disp. Rate	5 BPM	Mixing	0530	0602
Slurry Vol.	1.32 ³ Cu. Ft./Sk	Change Valves	0602	0605
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0605	0615
Water/Cement	6.25 Gal/SK			
Water Temp.	76°F			
Total Slurry Vol.	124.5	BBLS Cement		
Landed Plug @	700	PSI/Final Lift @	250	PSI
Pre-Flush W/	20	BBLS H ₂ O	Tax Reference Code	Sub Total
Displace W/	50.3	BBLS H ₂ O	State	CO 2.9%
Circulate	5	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		42			
1214/1218		Bulk Truck		42/42			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH, EVAN, ERNIE

Received By

Rusty Tucker

Customer or His Agent