

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

2588198

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100185

4. Contact Name: SHEILLA REED-HIGH

2. Name of Operator: ENCANA OIL & GAS (USA) INC

Phone: (720) 876-3678

3. Address: 370 17TH ST STE 1700

Fax: (720) 876-4678

City: DENVER State: CO Zip: 80202-

5. API Number 05-014-20710-00

6. County: BROOMFIELD

7. Well Name: SEARS

Well Number: 0-4-26

8. Location: QtrQtr: SWNW Section: 26 Township: 1N Range: 68W Meridian: 6

Footage at surface: Distance: 1794 feet Direction: FNL Distance: 596 feet Direction: FWL

As Drilled Latitude: 40.024499 As Drilled Longitude: -104.977997

GPS Data:

Data of Measurement: 07/21/2011 PDOP Reading: 2.6 GPS Instrument Operator's Name: PAT LINDERHOLM

** If directional footage at Top of Prod. Zone Dist.: 2518 feet. Direction: FNL Dist.: 87 feet. Direction: FWL

Sec: 26 Twp: 1N Rng: 68W

** If directional footage at Bottom Hole Dist.: 2481 feet. Direction: FNL Dist.: 117 feet. Direction: FWL

Sec: 26 Twp: 1N Rng: 68W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 06/02/2011 13. Date TD: 06/07/2011 14. Date Casing Set or D&A: 06/09/2011

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 8680 TVD** 8571 17 Plug Back Total Depth MD 8625 TVD** 8516

18. Elevations GR 5188 KB 5200

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL/DUAL IND/COMPENSATED DENSITY/COMPENSATED NEUTRON

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8		0	1,268	480	0	1,268	CALC
1ST	7+7/8	4+1/2		0	8,667	340	6,410	8,667	CBL

ADDITIONAL CEMENT

Cement work date: _____

Details of work:

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
STAGE TOOL	1ST	5,808	295	4,020	5,808

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,920		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,650		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	8,072		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	8,512		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: SHEILLA REED-HIGH

Title: OPERATIONS Date: 7/22/2011 Email: SHEILLA.REEDHIGH@ENCANA.COM

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
2588200	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
2588199	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
2588198	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)