



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199578

Date <u>5/4/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>34-35</u>	Lease <u>Badding</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme #15)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Ft. <u>1180</u>	
<u>Surface</u> <u>8 5/8" CG-24"</u>	Bottom of Surface	Ft. <u>1171</u>	
Plug	Plug Landed @ <u>1127</u>	Ft. <u>1450</u>	
Production	Pipe Landed @ <u>1171</u>	Ft. <u>2015</u>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>Type III</u>	740	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % <u>Fio-Cete 1/4 # Per Sack</u>				
Mileage Charge	192	Miles		
Fuel Surcharge	192	Miles		
Additional Cement		SKS		
Mixing Rate <u>4 BPM</u>	Pre-Flush	1920-	1926	
Disp. Rate <u>5 BPM</u>	Mixing	1926-	1958	
Slurry Vol. <u>1.32³ Cu. Ft./Sk</u>	Change Valves	1958-	2001	
Slurry Wt. <u>14.8 - 15.0 PPG</u>	Displacement	2001-	2015	
Water/Cement <u>6.25 Gal/SK</u>				
Water Temp. <u>53°F</u>				
Total Slurry Vol. <u>174</u>	BBLS Cement			
Landed Plug @ <u>800</u>	PSI/Final Lift @ <u>400</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>71.5</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>3</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>64</u>			
<u>1210/1218</u>		Bulk Truck		<u>64/64</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Dailas Justin Demetrio

Received By Rusty Tucker

Customer or His Agent