



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600105

Date <u>7/28/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>39-18</u>	Lease <u>Hudeo</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Patterson #189)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	FL	
<u>Surface</u>	<u>8 5/8" CSG-24"</u>	<u>964</u>	
	Bottom of Surface	FL	
		<u>953</u>	
Plug	Plug Landed @ <u>909</u>	FL	Time On <u>1055</u>
Production	Pipe Landed @ <u>953</u>	FL	Plug Down <u>1345</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>✓ Type III</u>	<u>600</u>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	<u>132</u>	Miles		
Fuel Surcharge	<u>132</u>	Miles		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush		
Disp. Rate	5 BPM	Mixing		
Slurry Vol.	1.32 ³ Cu. Ft./Sk	Change Valves		
Slurry Wt.	14.8 - 15.0 PPG	Displacement		
Water/Cement	6.25 Gal/SK			
Water Temp.	<u>92°F</u>			
Total Slurry Vol.	<u>141</u>	BBLS Cement		
Landed Plug @	<u>400</u>	PSI/Final Lift @ <u>200</u>	PSI	
Pre-Flush W/ <u>30</u>	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>58</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>6</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>44</u>			
<u>1214/1217</u>		Bulk Truck		<u>44/44</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Kenny - Demetrio

Received By

Danny H

Customer or His Agent