

**FORM
5**Rev
02/08**State of Colorado
Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400209536

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☐ Final completion ☒ Preliminary completion

1. OGCC Operator Number: 53650

4. Contact Name: Anna Walls

2. Name of Operator: MARATHON OIL COMPANY

Phone: (713) 296-3468

3. Address: 5555 SAN FELIPE

Fax: (713) 513-4394

City: HOUSTON State: TX Zip: 77056

5. API Number 05-123-33198-00

6. County: WELD

7. Well Name: Crow Valley 7-62-32

Well Number: 1M

8. Location: QtrQtr: NESE Section: 32 Township: 7N Range: 62W Meridian: 6

Footage at surface: Distance: 1390 feet Direction: FSL Distance: 2374 feet Direction: FEL

As Drilled Latitude: 40.526801 As Drilled Longitude: -104.345257

GPS Data:

Data of Measurement: 06/17/2011 PDOP Reading: 3.2 GPS Instrument Operator's Name: Adam Harmon

** If directional footage

at Top of Prod. Zone Distance: feet Direction: Distance: feet Direction:

Sec: Twp: Rng:

at Bottom Hole Distance: feet Direction: Distance: feet Direction:

Sec: Twp: Rng:

9. Field Name: WILDCAT

10. Field Number: 99999

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 05/26/2011 13. Date TD: 06/08/2011 14. Date Casing Set or D&A: 06/10/2011

15. Well Classification:

☐ Dry ☐ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☒ Observation

16. Total Depth MD 7609 TVD 7607 17 Plug Back Total Depth MD 7509 TVD 7508

18. Elevations GR 4919 KB 4949

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

Triple Combo, Sonic, CBL, Mud

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	17+1/2	16		0	90				
SURF	12+1/4	8+5/8	32	0	758	410	0	758	
1ST	7+7/8	5+1/2	20	0	7,601	900	418	7,601	

ADDITIONAL CEMENT

Cement work date: _____

Details of work:

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	3,586		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,396		<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	5,139		<input type="checkbox"/>	<input type="checkbox"/>	
SHARON SPRINGS	6,504		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	6,599		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	7,300		<input type="checkbox"/>	<input type="checkbox"/>	
DAKOTA	7,572		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Request to Keep ALL Well Data Confidential for the maximum timeframe.

Well is an observation monitor well, not a producing well. Well is currently T/A'd.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Anna Walls

Title: Adv Regulatory Compliance

Date:

Email: avwalls@marathonoil.com

Based on the information provided herein, this Drilling Completion Report (Form 5) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Attachment Check List

Att Doc Num	Name
400209695	LAS-CEMENT BOND
400209697	LAS-TRIPLE COMBINATION
400209699	LAS-SONIC
400209827	LAS-MUD
400210520	WELLBORE DIAGRAM
400215183	CEMENT JOB SUMMARY
400215184	CEMENT JOB SUMMARY
400215185	OTHER

Total Attach: 8 Files

General Comments

User Group Comment Comment Date

--	--	--

Total: 0 comment(s)