



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600020

Date <u>8-19-11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>14-16</u>	Lease <u>Cooley</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil &amp; Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Patterson #189)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Ft. <u>950</u>	
<u>Surface</u> <u>8 5/8" CSG-34"</u>	Bottom of Surface	Ft. <u>940</u>	
Plug	Plug Landed @ <u>896</u>	Ft. <u>14:15</u>	
Production	Pipe Landed @ <u>940</u>	Ft. <u>16:45</u>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>✓ Type III</u>	<u>590</u>	SKS		
Poz. Mix				
Calcium Chloride	<u>2.5</u>	%		
Gel % Flo-Cete 1/4 # Per Sack <u>800/2090</u>				
Mileage Charge <u>2044977</u>	<u>228</u>	Miles		
Fuel Surcharge	<u>228</u>	Miles		
Additional Cement		SKS		
Mixing Rate <u>4 BPM</u>	Pre-Flush	<u>16:01</u>	<u>16:07</u>	
Disp. Rate <u>5 BPM</u>	Mixing	<u>16:07</u>	<u>16:30</u>	
Slurry Vol. <u>1:32<sup>3</sup> Cu.Ft./Sk</u>	Change Valves	<u>16:30</u>	<u>16:33</u>	
Slurry Wt. <u>14.8-15.0 PPG</u>	Displacement	<u>16:33</u>	<u>16:45</u>	
Water/Cement <u>6.25 Gal/SK</u>				
Water Temp. <u>81°F</u>				
Total Slurry Vol. <u>138.7</u>	BBLS Cement			
Landed Plug @ <u>400</u>	PSI/Final Lift @ <u>200</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace W/ <u>57</u>	BBLS H <sub>2</sub> O	State <u>CO 2.9%</u>	Tax	
Circulate <u>5</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>76</u>			
<u>1216/1218</u>		Bulk Truck		<u>76/76</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Dallas, Kenny, Demetris

Received By Danny W  
Customer or His Agent