



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600003

Date	8-9-11	Well Owner	Kerr McGee	Well No.	16-30	Lease	BRYANT
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME #12)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	887		
Surface	8 5/8" CSG-24A	Bottom of Surface		Fl.	881		
Plug		Plug Landed @	837	Fl.	Time On	1500	
Production		Plug Landed @	881	Fl.	Plug Down	2000	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	560	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge 2030375.00	270	Miles		
Fuel Surcharge 800.12090	270	MILES		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	1905	1913	
Disp. Rate 5 BPM	Mixing	1913	1946	
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves	1946	1949	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	1949	2000	
Water/Cement 6.25 Gal/SK				
Water Temp. 74°F				
Total Slurry Vol. 131.6	BBLs Cement			
Landed Plug @ 400	PSI/Final Lift @ 300	PSI		
Pre-Flush W/ 30	BBLs H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 53.2	BBLs H ₂ O	State CO 2.9%	Tax	
Circulate 5	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		90			
1207/1217		Bulk Truck		90/90			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH, EVAN, ERUTE

Received By Customer or His Agent