

FORM
5A

Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400216089

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: <u>47120</u>	4. Contact Name: <u>CARA MAHLER</u>
2. Name of Operator: <u>KERR-MCGEE OIL & GAS ONSHORE LP</u>	Phone: <u>(720) 929-6029</u>
3. Address: <u>P O BOX 173779</u>	Fax: <u>(720) 929-7029</u>
City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80217-</u>	

5. API Number <u>05-123-15401-00</u>	6. County: <u>WELD</u>
7. Well Name: <u>RON GAULKEY GAS UNIT</u>	Well Number: <u>1</u>
8. Location: QtrQtr: <u>SESW</u> Section: <u>25</u> Township: <u>2N</u> Range: <u>68W</u> Meridian: <u>6</u>	
9. Field Name: _____	Field Code: _____

Completed Interval

FORMATION: J SAND

Status: TEMPORARILY ABANDONED

Treatment Date: 09/06/2011

Date of First Production this formation: 01/10/1992

Perforations Top: 8058 Bottom: 8104 No. Holes: 184 Hole size: 0.5

Provide a brief summary of the formation treatment:

Open Hole: ☐

SET CIBP @ 7678-7700.

This formation is commingled with another formation: ☐ Yes ☒ No**Test Information:**

Date: _____ Hours: _____ Bbls oil: _____ Mcf Gas: _____ Bbls H2O: _____

Calculated 24 hour rate: _____ Bbls oil: _____ Mcf Gas: _____ Bbls H2O: _____ GOR: _____

Test Method: _____ Casing PSI: _____ Tubing PSI: _____ Choke Size: _____

Gas Disposition: _____ Gas Type: _____ BTU Gas: _____ API Gravity Oil: _____

Tubing Size: _____ Tubing Setting Depth: _____ Tbg setting date: _____ Packer Depth: _____

Reason for Non-Production:

SET CIBP @ 7678-7700.

Date formation Abandoned: 09/06/2011 Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt _____

Bridge Plug Depth: 7700 Sacks cement on top: _____

FORMATION: NIOBRARA-CODELL

Status: PRODUCING

Treatment Date: 09/21/2011

Date of First Production this formation: 10/05/2011

Perforations Top: 7415 Bottom: 7648 No. Holes: 60 Hole size: 0.38

Provide a brief summary of the formation treatment:

Open Hole: ☐

CDL REPERF (9/6/11) 7630-7648 HOLES 18 SIZE .42 NB REPERF (9/6/2011) 7415-7510 HOLES 30 SIZE .42
Re-Frac Codell down 2-7/8" Tbg w/ Pkr ^ Nio w/ 206,438 gal Slickwater w/ 150,360# 40/70, 4,460# SB Excel.
Re-Frac Niobrara B & C down 2-7/8" Tbg w/ Pkr ^ Nio w/ 250 gal 15% HCl & 233,136 gal Slickwater w/ 200,520# 40/70, 4,060# SB Excel.

This formation is commingled with another formation: ☐ Yes ☒ No**Test Information:**

Date: 10/16/2011 Hours: 24 Bbls oil: 0 Mcf Gas: 16 Bbls H2O: 0

Calculated 24 hour rate: _____ Bbls oil: 0 Mcf Gas: 16 Bbls H2O: 0 GOR: 0

Test Method: FLOWING Casing PSI: 549 Tubing PSI: _____ Choke Size: _____

Gas Disposition: SOLD Gas Type: WET BTU Gas: 1309 API Gravity Oil: 49

Tubing Size: _____ Tubing Setting Depth: _____ Tbg setting date: _____ Packer Depth: _____

Reason for Non-Production:

Date formation Abandoned: _____ Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt _____

Bridge Plug Depth: _____ Sacks cement on top: _____

Comment:

CHOKE N/A

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: CARA MAHLER

Based on the information provided herein, this Completed Interval Report (Form 5A) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Director of COGCCDate:

Attachment Check List

Att Doc Num	Name

Total Attach: 0 Files

General Comments

User GroupCommentComment Date

--	--	--

Total: 0 comment(s)