

FORM
2Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

- 1.
- ☒
- Drill,
- ☐
- Deepen,
- ☐
- Re-enter,
- ☐
- Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐Refiling ☐Sidetrack ☐

Document Number:

400186526

PluggingBond SuretyID

20030009

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: MARI CLARK Phone: (303)228-4413 Fax: (303)228-4286

Email: mclark@nobleenergyinc.com

7. Well Name: NOVACEK C Well Number: 28-27D

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 7575

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 21 Twp: 4N Rng: 64W Meridian: 6

Latitude: 40.292230 Longitude: -104.549390

Footage at Surface: 566 feet FNL/FSL 830 feet FEL/FWL
FSL FEL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4760 13. County: WELD

14. GPS Data:

Date of Measurement: 06/17/2011 PDOP Reading: 1.8 Instrument Operator's Name: ADAM KELLY

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
75 FNL 1320 FEL 75 FNL 1320 FEL
Sec: 28 Twp: 4N Rng: 64W Sec: 28 Twp: 4N Rng: 64W16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 554 ft

18. Distance to nearest property line: 195 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 830 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407-87	160	GWA
NIOBRARA	NBRR	407-87	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 2003001223a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

SECTION 28: NE/4, T4N-R64W

25. Distance to Nearest Mineral Lease Line: 75 ft

26. Total Acres in Lease: 160

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/2	8+5/8	24	0	790	240	790	0
1ST	7+7/8	4+1/2	11.6	0	7,575	706	7,575	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. 1ST STRING TOP OF CEMENT = 200' ABOVE NIOBRARA. UNIT CONFIGURATION = S/2SE OF SECTION 21 & THE N/2NE OF SECTION 28. WELL IS TO BE TWINNED WITH EXISTING LEONARD C21-16.

34. Location ID: 310294

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: MARI CLARK

Title: REG. ANALYST II Date: 9/26/2011 Email: mclark@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline

Director of COGCC Date: 10/19/2011

API NUMBER

05 123 34562 00

Permit Number: _____ Expiration Date: 10/18/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1)Note surface casing setting depth change from 650' to 790'. Increase cement coverage accordingly and cement to surface.
- 2)Provide 24 hour notice of MIRU to Jim Precup via e-mail at jim.precup@state.co.us.
- 3)Comply with Rule 317.i and provide cement coverage from the end of the production casing to a minimum of 200' above the Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with a cement bond log.
- 4)Comply with Rule 321. Run and submit Directional Survey from the end of production casing to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
2507005	SURFACE CASING CHECK
400186526	FORM 2 SUBMITTED
400208259	DEVIATED DRILLING PLAN
400208260	30 DAY NOTICE LETTER
400208261	WELL LOCATION PLAT
400208262	PROPOSED SPACING UNIT

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	No LGD or public comment received; final review completed.	10/18/2011 3:10:54 PM
Permit	Returned to draft. Missing location ID #.	9/27/2011 8:56:43 AM

Total: 2 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Material Handling and Spill Prevention	Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.
General Housekeeping	Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pickup trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.
Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) General Permit No. COR-038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location, and will remain in place until the pad reaches final reclamation.

Total: 3 comment(s)