

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number: 400195833			
PluggingBond SuretyID 20030009			

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐
Sidetrack ☐

3. Name of Operator: NOBLE ENERGY INC 4. COGCC Operator Number: 100322
5. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202
6. Contact Name: Justin Garrett Phone: (303)228-4449 Fax: (303)228-4286
Email: JGGarrett@nobleenergyinc.com
7. Well Name: Wells Ranch USX Well Number: AA25-69HN
8. Unit Name (if appl): _____ Unit Number: _____
9. Proposed Total Measured Depth: 11004

WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 25 Twp: 6N Rng: 63W Meridian: 6
Latitude: 40.461990 Longitude: -104.393530

Footage at Surface: 1002 feet FNL 302 feet FWL

11. Field Name: Crow Creek Field Number: 13610
12. Ground Elevation: 4815 13. County: WELD

14. GPS Data:

Date of Measurement: 07/12/2011 PDOP Reading: 1.9 Instrument Operator's Name: Adam Kelly

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
293 FNL 804 FWL 300 FNL 535 FEL
Sec: 25 Twp: 6N Rng: 63W Sec: 25 Twp: 6N Rng: 63W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 5281 ft

18. Distance to nearest property line: 302 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 370 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	407-87	320	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Noble Energy Inc. certifies that the lease(s) shall be committed to the unit. Please see attached lease map.

25. Distance to Nearest Mineral Lease Line: 535 ft

26. Total Acres in Lease: 4480

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Closed loop

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	16+0/0	15+0/0		0	100	6	100	0
SURF	13+3/4	9+5/8	36	0	500	269	500	0
1ST	8+3/4	7+0/0	26	0	7,056	975	7,056	
1ST LINER	6+1/8	4+1/2	11.6	5844	11,004			

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments First String top of cement will be 200' above Niobrara formation. The production liner will be hung off inside 7" casing. Distance to nearest building, public road, above ground utility, & railroad is greater than 1 mile. Well is part of a 4-well pad consisting of the proposed Wells Ranch USX AA25-67-1HN (Doc #400194712), Wells Ranch USX AA25-67HN (Doc #400194713), Wells Ranch USX AA25-68-1HN (Doc #400194714), & Wells Ranch USX AA25-69HN (Doc #400195833), multi-well plan attached. The production facilities for the proposed pad are part of the proposed location approx. 1600' S of the pad site, doc #400185150. Unit Configuration = N/2N/2 Sec 25 & S/2S/2 Sec 24. *This permit is being submitted with the intent that it will be subject to the new rule 318A; please delay approval until said rule is in effect.* Wellhead is to be located outside of a GWA drilling window and will be located more than 50' from an existing well location. Noble requests an exception location to 318Aa, 318Ac: Exception request and waiver attached.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Justin Garrett

Title: Regulatory Specialist Date: 8/19/2011 Email: JDGarrett@nobleenergyinc.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nash

Director of COGCC Date: 10/19/2011

API NUMBER

05 123 34566 00

Permit Number: _____ Expiration Date: 10/18/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Operator must meet water well sampling requirements per Rule 318A

- 1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
400195833	FORM 2 SUBMITTED
400198050	30 DAY NOTICE LETTER
400198051	PLAT
400198052	DEVIATED DRILLING PLAN
400198053	LEASE MAP
400198054	MULTI-WELL PLAN
400198055	SURFACE AGRMT/SURETY
400198057	LEASE MAP
400198058	EXCEPTION LOC WAIVERS
400198059	EXCEPTION LOC REQUEST
400198060	PROPOSED SPACING UNIT

Total Attach: 11 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	No LGD or public comment received; final review completed.	10/18/2011 4:00:25 PM

Total: 1 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Material Handling and Spill Prevention	Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.
General Housekeeping	Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pickup trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.
Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) General Permit No. COR- 038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location, and will remain in place until the pad reaches final reclamation.

Total: 3 comment(s)