

FORM
5A

Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400216797

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 10334
2. Name of Operator: SLAWSON EXPLORATION COMPANY INC
3. Address: 1675 BROADWAY - SUITE 1600
City: DENVER State: CO Zip: 80202
4. Contact Name: CLAYTON DOKE
Phone: (970) 669-7411
Fax: (970) 669-4077

5. API Number 05-123-32006-00
6. County: WELD
7. Well Name: OUTLAW
Well Number: 16-11-66
8. Location: QtrQtr: SESE Section: 16 Township: 11N Range: 66W Meridian: 6
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING

Treatment Date: 01/14/2011 Date of First Production this formation: 02/12/2011
Perforations Top: 8902 Bottom: 12391 No. Holes: Hole size:

Provide a brief summary of the formation treatment: Open Hole: ☒

13 stages, 41,506 bbls, 1,312,421 lbs of proppant (15,360 100 Mesh, 24,302 40/70, 1,288,119 20/40)
Interval 1 - 4612 bbls, 245,332 lbs of proppant (20,076 40/70, 225,256 20/40)
Interval 2 - 4744 bbls, 116,928 lbs of proppant (2,462 40/70, 114,466 20/40)
Interval 3 - 1314 bbls, 1,764 lbs of proppant (1,764 40/70)
Interval 4 - 3127 bbls, 153,829 lbs of proppant (10,504 100 Mesh, 143,325 20/40)
Interval 5 - 482 bbls, 5,126 lbs of proppant (5,126 100 Mesh)
Interval 6 - 1117 bbls, 4,442 lbs of proppant (4,442 20/40)
Interval 7 - 3386 bbls, 133,538 lbs of proppant (133,538 20/40)
Interval 8 - 4593.9 bbls, 151,024 lbs of proppant (151,024 20/40)
Interval 9 - 3364.7 bbls, 134,963 lbs of proppant (134,963 20/40)
Interval 10 - 3451.8 bbls, 4,152 lbs of proppant (4,152 20/40)
Interval 11 - 4409.7 bbls, 69,741 lbs of proppant (69,741 20/40)
Interval 12 - 3310.2 bbls, 127,604 lbs of proppant (127,604 20/40)
Interval 13 - 3594.1 bbls, 179,608 lbs of proppant (179,608 20/40)

This formation is commingled with another formation: ☐ Yes ☒ No

Test Information:

Date: 04/18/2011 Hours: 24 Bbls oil: 5 Mcf Gas: 0 Bbls H2O: 68
Calculated 24 hour rate: Bbls oil: 5 Mcf Gas: 0 Bbls H2O: 68 GOR:
Test Method: Pumping Casing PSI: 0 Tubing PSI: 0 Choke Size:
Gas Disposition: FLARED Gas Type: DRY BTU Gas: 1300 API Gravity Oil: 33
Tubing Size: 2 + 7/8 Tubing Setting Depth: 7727 Tbg setting date: 01/24/2011 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt
Bridge Plug Depth: Sacks cement on top:

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: CLAYTON DOKE

Title: CONSULTANT

Date: _____

Email : cdoke@petersonenergy.com

Based on the information provided herein, this Completed Interval Report (Form 5A) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____

Director of COGCC

Date: _____

Attachment Check List

Att Doc Num	Name

Total Attach: 0 Files

General Comments

User Group **Comment** **Comment Date**

--	--	--

Total: 0 comment(s)