



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199620

Date	5-9-11	Well Owner	Kerr McGee	Well No.	12-355X	Lease	BADDING
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME-15)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	FL 1200				
Surface	8 5/8" CS - 24 #	Bottom of Surface	FL 1190				
Plug		Plug Landed @	1145	FL	Time On	1575	
Production		Pipe Landed @	1190	FL	Plug Down	2000	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	750	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	192	Miles		
Fuel Surcharge	192	miles		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	1850 - 1858	
Disp. Rate	5 BPM	Mixing	1858 - 1942	
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	1942 - 1945	
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1945 - 2000	
Water/Cement	6.25 Gal/SK			20453330 NDL
Water Temp.	60°F			800/2090
Total Slurry Vol.	176.3	BBLs Cement		
Landed Plug @	900	PSI/Final Lift @ 400	PSI	
Pre-Flush W/	30	BBLs H ₂ O	Tax Reference Code	Sub Total
Displace W/	72.8	BBLs H ₂ O	State CO 2.9%	Tax
Circulate	5	BBLs Cement	Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		64			
1216/1218		Bulk Truck		64/64			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Joe, Josh, Evan

Received By *Robert Tucker*
Customer or His Agent