



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600012

Date	8-24-11	Well Owner	Kerr McGee	Well No.	23-16	Lease	COOLEY
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (PAT-189)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	952		
Surface	8 7/8" CSG-24H	Bottom of Surface		Fl.	942		
Plug		Plug Landed @	898	Fl.	Time On	1300	
Production		Pipe Landed @	942	Fl.	Plug Down	1545	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	590	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cote 1/4 # Per Sack	80012090 MLC			
Mileage Charge	228	Miles		
Fuel Surcharge	228	MILES		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	1448	1456
Disp. Rate	5 BPM	Mixing	1456	1531
Slurry Vol.	1.32 Cu.Ft./Sk	Change Valves	1531	1534
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1534	1545
Water/Cement	6.25 Gal/SK			
Water Temp.	80°F			
Total Slurry Vol.	138.7	BBLS Cement		
Landed Plug @	300	PSI/Final Lift @	280	PSI
Pre-Flush W/	30	BBLS H ₂ O	Tax Reference Code	Sub Total
Displace W/	57.1	BBLS H ₂ O	State CO 2.9%	Tax
Circulate	5	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		76			
1216/1218		Bulk Truck		76/76			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH, EVAN, ERNIE

Received By Dan
Customer or His Agent