



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600112

Date <u>8-14-11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>11-15</u>	Lease <u>Ricks</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme #14)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job <u>Surface</u>	Depth <u>930</u>	FL <u>930</u>	
<u>8 1/8" CSC-24"</u>	Bottom of Surface	FL <u>920</u>	
Plug	Plug Landed @ <u>898</u>	FL	Time On <u>18:00</u>
Production	Pipe Landed @ <u>920</u>	FL	Plug Down <u>22:00</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>✓ Type III</u>	<u>580</u>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % <u>Fio-Cete 1/4 # Per Sack</u>				
Mileage Charge	<u>132</u>	Miles		
Fuel Surcharge	<u>132</u>	Miles		
Additional Cement	<u>60</u>	SKS		
Mixing Rate: <u>4 BPM</u>	Pre-Flush	<u>21:14</u>	<u>21:20</u>	
Disp. Rate: <u>5 BPM</u>	Mixing	<u>21:20</u>	<u>21:45</u>	
Slurry Vol. <u>1,323 Cu. Ft./Sk</u>	Change Valves	<u>21:45</u>	<u>21:48</u>	
Slurry Wt. <u>14.8 - 15.0 PPG</u>	Displacement	<u>21:48</u>	<u>22:00</u>	
Water/Cement: <u>6.25 Gal/SK</u>				
Water Temp. <u>85°F</u>				
Total Slurry Vol. <u>150.5</u>	BBLS Cement			
Landed Plug @ <u>800</u>	PSI/Final Lift @ <u>400</u>	PSI		
Pre-Flush Wt <u>30</u>	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace Wt <u>57</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>4</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>44</u>			
<u>1217/1218</u>		Bulk Truck		<u>44/44</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Dalks, Kenny, Dome drio

Received By

Cody Sanchez
Customer or His Agent