



DE	ET	OE	ES
----	----	----	----

Document Number:
 400214208
 PluggingBond SuretyID
 20010124

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL
 OIL GAS COALBED OTHER _____
 SINGLE ZONE MULTIPLE COMMINGLE

Refiling
 Sidetrack

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP 4. COGCC Operator Number: 47120
 5. Address: P O BOX 173779
 City: DENVER State: CO Zip: 80217-3779
 6. Contact Name: Rebecca Heim Phone: (720)929-6361 Fax: (720)929-7361
 Email: rebecca.heim@anadarko.com
 7. Well Name: RICE Well Number: 2N-33HZ
 8. Unit Name (if appl): _____ Unit Number: _____
 9. Proposed Total Measured Depth: 11733

WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 33 Twp: 3N Rng: 66W Meridian: 6
 Latitude: 40.175955 Longitude: -104.779836
 Footage at Surface: 614 feet FNL/FSL FSL 1983 feet FEL/FWL FEL
 11. Field Name: WATTENBERG Field Number: 90750
 12. Ground Elevation: 4941 13. County: WELD

14. GPS Data:
 Date of Measurement: 08/05/2011 PDOP Reading: 2.2 Instrument Operator's Name: OWEN McKEE

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**
 Footage at Top of Prod Zone: FNL/FSL 594 FSL 2123 FEL FEL Bottom Hole: FNL/FSL 460 FNL 2130 FEL FEL
 Sec: 33 Twp: 3N Rng: 66W Sec: 33 Twp: 3N Rng: 66W

16. Is location in a high density area? (Rule 603b)? Yes No
 17. Distance to the nearest building, public road, above ground utility or railroad: 580 ft
 18. Distance to nearest property line: 615 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1297 ft

LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		160	W/2E/2

21. Mineral Ownership: Fee State Federal Indian Lease #: _____
 22. Surface Ownership: Fee State Federal Indian
 23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____
 23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No
 23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Please see attached Oil and Gas Lease.

25. Distance to Nearest Mineral Lease Line: 460 ft 26. Total Acres in Lease: 160

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36.0	0	700	350	700	
1ST	8+3/4	7	26.0	0	7,560	740	7,560	
1ST LINER	6+1/8	4+1/2	11.6	6499	11,733		11,733	

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments No conductor casing will be used.

34. Location ID: 327237

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Rebecca Heim

Title: Regulatory Analyst II Date: _____ Email: DJRegulatory@anadarko.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400214211	DEVIATED DRILLING PLAN
400214212	PLAT
400214213	TOPO MAP
400214214	30 DAY NOTICE LETTER
400214215	SURFACE AGRMT/SURETY
400214216	OIL & GAS LEASE
400214217	OIL & GAS LEASE
400214218	PROPOSED SPACING UNIT

Total Attach: 8 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	<p>1. At least seven (7) days prior to fracture stimulation, the operator is to notify all operators of non-operated wells within 300 feet of the wellbore to be fracture stimulated of the anticipated date stimulation date and the recommended best management practice to shut-in all wells within 300' of the stimulated wellbore completed in the same formation.</p> <p>2. The operator will monitor the bradenhead pressure of all wells operated by the operator within 300 feet of the well to be fracture stimulated.</p> <p>3. Bradenhead pressure gauges are to be installed 24 hours prior to stimulation. The gauges are to read at least once during every 24-hour period until 24-hours after stimulation is completed (post flowback). The gauges are to be of the type able to read current pressure and record the maximum encountered pressure in a 24-hour period. The gauge is to be reset between each 24-hour period. The pressures are to be recorded and saved. Alternate electronic measurement may be used to record the prescribed pressures. Data shall be kept for a period of one year.</p> <p>If at any time during stimulation or the 24-hour post-stimulation period, the bradenhead annulus pressure of the treatment well or offset wells increases more than 200 psig, as per Rule 341, the operator of the well being stimulated shall verbally notify the Director as soon as practicable, but no later than twenty-four (24) hours following the incident. Within fifteen (15) days after the occurrence, the operator shall submit a Sundry Notice, Form 4, giving all details, including corrective actions taken</p>

Total: 1 comment(s)