

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400211235

PluggingBond SuretyID

20030107

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY LLC

4. COGCC Operator Number: 96850

5. Address: 1001 17TH STREET - SUITE #1200

City: DENVER State: CO Zip: 80202

6. Contact Name: Greg Davis Phone: (303)606-4071 Fax: (303)629-8268

Email: Greg.J.Davis@Williams.com

7. Well Name: Hoeppli Well Number: RWF 632-36

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 8942

WELL LOCATION INFORMATION

10. QtrQtr: SWNE Sec: 36 Twp: 6S Rng: 94W Meridian: 6

Latitude: 39.482415 Longitude: -107.835812

Footage at Surface: 2573 feet FNL/FSL 2559 feet FEL/FWL  
FNL FEL

11. Field Name: Rulison Field Number: 75400

12. Ground Elevation: 6528.9 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 06/27/2008 PDOP Reading: 6.0 Instrument Operator's Name: J. Kirkpatrick

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
2638 FNL 1835 FEL 2638 FNL 1835 FEL  
Sec: 36 Twp: 6S Rng: 94W Sec: 36 Twp: 6S Rng: 94W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 991 ft

18. Distance to nearest property line: 991 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 960 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	139-66	640	All

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

25. Distance to Nearest Mineral Lease Line: 465 ft

26. Total Acres in Lease: 800

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Re-use and evaporation

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	18	48#	0	45	25	45	0
SURF	13+1/2	9+5/8	32.3#	0	1,109	300	1,109	0
1ST	7+7/8	4+1/2	11.6#	0	8,942	925	8,942	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Cement 200' above uppermost mesaverde sand. Location has been constructed. Pits are constructed. No pad expansion is necessary. No rig on location. Closed loop There have been no changes to drilling or lease conditions since the original Form 2 was filed. Not in an RSO.

34. Location ID: 335050

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Greg Davis

Title: Supervisor Permits Date: 10/4/2011 Email: Greg.J.Davis@Williams.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nash

Director of COGCC Date: 10/28/2011

#### API NUMBER

05 045 18203 00

Permit Number: \_\_\_\_\_ Expiration Date: 10/27/2013

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1)COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2)GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 180 FEET DEEP.

### **Attachment Check List**

Att Doc Num	Name
400211235	FORM 2 SUBMITTED

Total Attach: 1 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	off hold--changed nearest well footage to 960' and removed "see attached" under lease description per oper.'s instructions. LGD/pub. comm. waived. Final Comprehensive Review Status--passed.	10/27/2011 2:47:44 PM
Permit	on hold--req'd clarification of nearest well distance	10/27/2011 10:54:14 AM

Total: 2 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>

Total: 0 comment(s)