



#### TEBO 32-2 PAD:

TOP OF PAD ELEVATION = 5923.0

CUT AND FILL SLOPES: 3:1

EARTHWORK SHRINKAGE AND COMPACTION FACTOR: 15%

#### PAD EARTHWORK VOLUMES:

TOTAL CUT: 26,560 CU. YDS.

TOTAL FILL: 13,540 x 1.15 = 15,570 CU. YDS.

400' PAD AREA: 3.67 ACRES

TOTAL DISTURBED AREA: 5.09 ACRES



SCALE: 1" = 100'

PREPARED FOR: CONOCOPHILLIPS COMPANY, OCTOBER 10, 2011

## PROPOSED WELL PAD LAYOUT

### TEBO 32-2

SECTION 32, TOWNSHIP 4 SOUTH, RANGE 64 WEST OF THE 6TH PM  
ARAPAHOE COUNTY, COLORADO

**ConocoPhillips**

**CVL**

CONSULTANTS OF COLORADO, INC.  
CIVIL ENGINEERING LAND SURVEYING

7901 E. Belleview Avenue  
Suite 150  
Englewood, CO 80111  
Tel: (720) 482-9526  
Fax: (720) 482-9546