



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600109

Date <u>8/9/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>17-6</u>	Lease <u>Lee</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil &amp; Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme #15)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job <u>Surface</u>	Depth <u>853</u>	FL <u>813</u>	
<u>8 5/8" OSB-24"</u>	Bottom of Surface	FL <u>813</u>	
Plug	Plug Landed @ <u>769</u>	FL	Time On <u>0900</u>
Production	Pipe Landed @ <u>813</u>	FL	Plug Down <u>1215</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>✓ Type III</u>	510	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge <u>3049646 DRL</u>	126	Miles		
Fuel Surcharge <u>6002090</u>	126	Miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush 1133	1139		
Disp. Rate 5 BPM	Mixing 1139-	1202		
Slurry Vol. 1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves 1202-	1205		
Slurry Wt. 14.8 - 15.0 PPG	Displacement 1205-	1215		
Water/Cement 6.25 Gal/SK				
Water Temp. <u>85°F</u>				
Total Slurry Vol. 120	BBLS Cement			
Landed Plug @ 400	PSI/Final Lift @ 200	PSI		
Pre-Flush W/ 30	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace W/ 49	BBLS H <sub>2</sub> O	State CO 2.9%	Tax	
Circulate 3	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1008		Pump Truck		42			
1216/1218		Bulk Truck		42/42			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Kenny & Demetrio

Received By John Salas  
Customer or His Agent