



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 600125

|   |                              |                     |                       |
|---|------------------------------|---------------------|-----------------------|
| Date <b>8/2/11</b>                                    | Well Owner <b>Kerr McGee</b> | Well No. <b>7-6</b> | Lease <b>LEE</b>      |
| County <b>weld</b>                                    | State <b>Colorado</b>        |                     |                       |
| Charge to <b>Kerr McGee Oil &amp; Gas Onshore, LP</b> |                              |                     |                       |
| Address <b>1999 Broadway, Suite 3700</b>              | <b>(Xtreme 15)</b>           |                     |                       |
| City, State Zip <b>Denver, Colorado 80202</b>         |                              |                     |                       |
| Type of Job   | Depth                        | FL                  |                       |
| <b>Surface</b>  | <b>85 1/2 CS6 #24</b>        | <b>865</b>          |                       |
|   | Bottom of Surface            | FL                  |                       |
|   |                              | <b>855</b>          |                       |
| Plug  | Plug Landed @ <b>811</b>     | Ft.                 | Time On <b>1100</b>   |
| Production  | Pipe Landed @ <b>855</b>     | Ft.                 | Plug Down <b>0230</b> |

| Description                    | Qty.                        | Meas.                       | Unit Price           | Amount      |
|--------------------------------|-----------------------------|-----------------------------|----------------------|-------------|
| Set Up Charge                  | 1                           |                             |                      |             |
| Cement Neat <b>TYPE III</b>    | <b>540</b>                  | SKS                         |                      |             |
| Poz. Mix                       |                             |                             |                      |             |
| Calcium Chloride               | 2.5                         | %                           |                      |             |
| Gel % Flo-Crete 1/4 # Per Sack |                             |                             |                      |             |
| Mileage Charge                 | <b>126</b>                  | Miles                       |                      |             |
| Fuel Surcharge                 | <b>126</b>                  | Miles                       |                      |             |
| Additional Cement              |                             | SKS                         |                      |             |
| Mixing Rate                    | 4 BPM                       | Pre-Flush                   | <b>0141</b>          | <b>0115</b> |
| Disp. Rate                     | 5 BPM                       | Mixing                      | <b>0145</b>          | <b>0217</b> |
| Slurry Vol.                    | 1.32 <sup>3</sup> Cu.Ft./Sk | Change Valves               | <b>0217</b>          | <b>0220</b> |
| Slurry Wt.                     | 14.8 - 15.0 PPG             | Displacement                | <b>0220</b>          | <b>0230</b> |
| Water/Cement                   | 6.25 Gal/SK                 |                             |                      |             |
| Water Temp.                    | <b>68°F</b>                 |                             |                      |             |
| Total Slurry Vol.              | <b>126.9</b>                | BBLS Cement                 |                      |             |
| Landed Plug @                  | <b>850</b>                  | PSI/Final Lift @ <b>300</b> | PSI                  |             |
| Pre-Flush W/                   | <b>20</b>                   | BBLS H <sub>2</sub> O       | Tax Reference Code   | Sub Total   |
| Displace W/                    | <b>51.5</b>                 | BBLS H <sub>2</sub> O       | State <b>CO 2.9%</b> | Tax         |
| Circulate                      | <b>6</b>                    | BBLS Cement                 |                      | Total       |

| Truck No.        | Code | State Mileage | Nebraska | Colorado     | Wyoming | Other | Total Mileage |
|------------------|------|---------------|----------|--------------|---------|-------|---------------|
| <b>1201</b>      |      | Pump Truck    |          | <b>42</b>    |         |       |               |
| <b>1207/1218</b> |      | Bulk Truck    |          | <b>42/42</b> |         |       |               |

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **Jim, Adam, Steve, Chris**

Received By

Customer or His Agent