

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400219608

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 47120

4. Contact Name: Cindy Vue

2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6832

3. Address: P O BOX 173779

Fax: (720) 929-7832

City: DENVER State: CO Zip: 80217-

5. API Number 05-123-32587-00

6. County: WELD

7. Well Name: COOK

Well Number: 2-9

8. Location: QtrQtr: SENW Section: 9 Township: 2N Range: 65W Meridian: 6

Footage at surface: Distance: 2406 feet Direction: FNL Distance: 2623 feet Direction: FWL

As Drilled Latitude: 40.153919 As Drilled Longitude: -104.668932

GPS Data:

Date of Measurement: 08/24/2011 PDOP Reading: 3.5 GPS Instrument Operator's Name: Renee Doiron

** If directional footage at Top of Prod. Zone Dist.: 567 feet. Direction: FNL Dist.: 2093 feet. Direction: FEL

Sec: 9 Twp: 2N Rng: 65W

** If directional footage at Bottom Hole Dist.: 570 feet. Direction: FNL Dist.: 2093 feet. Direction: FEL

Sec: 9 Twp: 2N Rng: 65W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 05/30/2011 13. Date TD: 06/01/2011 14. Date Casing Set or D&A: 06/02/2011

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7765 TVD** 7343 17 Plug Back Total Depth MD 7739 TVD** 7317

18. Elevations GR 4873 KB 4888

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CD-CN-ML, HRI; CBL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24#	0	739	470	15	739	CALC
1ST	7+7/8	4+1/2	11.6#	0	7,755	600	3,976	7,755	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: 06/02/2011

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	3,965	450	580	4,000
SQUEEZE	1ST	3,977	25	3,977	4,000

Details of work:

6/2/2011 -CMT STAGE TOOL WITH 450 SX CMT.
8/17/2011 -PUMP 25 SX BALANCE PLUG ACROSS DV TOOL @ 3977'

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	4,294		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,658		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,340		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,594		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,616		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Cindy Vue

Title: Regulatory Analyst II Date: _____ Email: Cindy.Vue@anadarko.com

The subreport 'subreport3' could not be found at the specified location W:\inetpub\Net\Reports\AttachListNew.rdlc. Please

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)