

FORM  
5Rev  
02/08

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400220067

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100322

4. Contact Name: EILEEN ROBERTS

2. Name of Operator: NOBLE ENERGY INC

Phone: (303) 2284330

3. Address: 1625 BROADWAY STE 2200

Fax: (303) 2284286

City: DENVER State: CO Zip: 80202

5. API Number 05-123-33552-00

6. County: WELD

7. Well Name: PIONEER USX

Well Number: Y07-07D

8. Location: QtrQtr: NESE Section: 7 Township: 2N Range: 64W Meridian: 6

Footage at surface: Distance: 1924 feet Direction: FSL Distance: 612 feet Direction: FEL

As Drilled Latitude: 40.150940 As Drilled Longitude: -104.587060

## GPS Data:

Date of Measurement: 06/30/2011 PDOP Reading: 3.6 GPS Instrument Operator's Name: Paul Tappy

\*\* If directional footage at Top of Prod. Zone Dist.: 1898 feet. Direction: FNL Dist.: 1958 feet. Direction: FEL

Sec: 7 Twp: 2N Rng: 64W

\*\* If directional footage at Bottom Hole Dist.: 1898 feet. Direction: FNL Dist.: 1958 feet. Direction: FEL

Sec: 7 Twp: 2N Rng: 64W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 06/24/2011 13. Date TD: 06/27/2011 14. Date Casing Set or D&amp;A: 06/28/2011

## 15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7702 TVD\*\* 7263 17 Plug Back Total Depth MD 7652 TVD\*\* 7213

18. Elevations GR 4860 KB 4875

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

## 19. List Electric Logs Run:

CBL/GRL/CCL/VDL, CDL/CNL/ML, HRIL.

## 20. Casing, Liner and Cement:

## CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24.00	0	864	370	0	875	
1ST	7+7/8	4+1/2	11.60	0	7,694	620	900	7,694	CBL

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____					
Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
Details of work:					

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
NIOBRARA	7,212		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,492		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,515		<input type="checkbox"/>	<input type="checkbox"/>	
GREENHORN	7,605		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Eileen Roberts

Title: Regulatory Specialist Date: \_\_\_\_\_ Email: eroberts@nobleenergyinc.com

The subreport 'subreport3' could not be found at the specified location W:\Inetpub\Net\Reports\AttachListNew.rdlc. Please

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)