

FORM
2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400217814

PluggingBond SuretyID

20010124

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: Rebecca Heim Phone: (720)929-6361 Fax: (720)929-7361
Email: rebecca.heim@anadarko.com

7. Well Name: WEISS Well Number: 29N-33HZ

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 11758

WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 33 Twp: 3N Rng: 66W Meridian: 6

Latitude: 40.176157 Longitude: -104.789531

Footage at Surface: 712 feet FNL/FSL 586 feet FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4914 13. County: WELD

14. GPS Data:

Date of Measurement: 08/05/2011 PDOP Reading: 2.2 Instrument Operator's Name: OWEN McKEE

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 797 FSL 1107 FWL 460 FEL/FWL 1220 FWL FWL
Sec: 33 Twp: 3N Rng: 66W Sec: 33 Twp: 3N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 546 ft

18. Distance to nearest property line: 350 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 560 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NI0BRARA	NBRR		320	W/2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Please see attached Oil and Gas Lease.

25. Distance to Nearest Mineral Lease Line: 460 ft

26. Total Acres in Lease: 5719

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36.0	0	700	350	700	
1ST	8+3/4	7	26.0	0	7,563	740	7,563	
1ST LINER	6+1/8	4+1/2	11.6	6495	11,758		11,758	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments No conductor casing will be used.

34. Location ID: 333181

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Rebecca Heim

Title: Regulatory Analyst II

Date: 10/28/2011

Email: DJRegulatory@anadarko.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400217814	FORM 2 SUBMITTED
400217818	PLAT
400217819	TOPO MAP
400217820	30 DAY NOTICE LETTER
400217821	SURFACE AGRMT/SURETY
400217822	OIL & GAS LEASE
400217823	PROPOSED SPACING UNIT
400219277	OTHER
400220145	DEVIATED DRILLING PLAN

Total Attach: 9 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	<p>1. At least seven (7) days prior to fracture stimulation, the operator is to notify all operators of non-operated wells within 300 feet of the wellbore to be fracture stimulated of the anticipated date stimulation date and the recommended best management practice to shut-in all wells within 300' of the stimulated wellbore completed in the same formation.</p> <p>2. The operator will monitor the bradenhead pressure of all wells operated by the operator within 300 feet of the well to be fracture stimulated.</p> <p>3. Bradenhead pressure gauges are to be installed 24 hours prior to stimulation. The gauges are to read at least once during every 24-hour period until 24-hours after stimulation is completed (post flowback). The gauges are to be of the type able to read current pressure and record the maximum encountered pressure in a 24-hour period. The gauge is to be reset between each 24-hour period. The pressures are to be recorded and saved. Alternate electronic measurement may be used to record the prescribed pressures. Data shall be kept for a period of one year.</p> <p>If at any time during stimulation or the 24-hour post-stimulation period, the bradenhead annulus pressure of the treatment well or offset wells increases more than 200 psig, as per Rule 341, the operator of the well being stimulated shall verbally notify the Director as soon as practicable, but no later than twenty-four (24) hours following the incident. Within fifteen (15) days after the occurrence, the operator shall submit a Sundry Notice, Form 4, giving all details, including corrective actions taken</p>

Total: 1 comment(s)