

FORM
5A

Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400219502

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120 4. Contact Name: Cindy Vue
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6832
3. Address: P O BOX 173779 Fax: (720) 929-7832
City: DENVER State: CO Zip: 80217-

5. API Number 05-123-33293-00 6. County: WELD
7. Well Name: LEE Well Number: 7-6
8. Location: QtrQtr: NWNE Section: 6 Township: 2N Range: 65W Meridian: 6
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA-CODELL Status: PRODUCING

Treatment Date: 10/07/2011 Date of First Production this formation: 10/13/2011
Perforations Top: 7324 Bottom: 7558 No. Holes: 126 Hole size: 0.38

Provide a brief summary of the formation treatment: Open Hole: ☐

NB PERF 7324-7388 HOLES 62 SIZE 0.47 CD PERF 7542-7558 HOLES 64 SIZE 0.38
Frac Niobrara B & C down 4-1/2" Csg w/ 250 gal 15% HCl & 248,852 gal Slickwater w/ 200,630# 40/70, 4,000# SB Excel
Frac Codell down 4-1/2" Csg w/ 197,358 gal Slickwater w/ 150,630# 40/70, 4,000# SB Excel

This formation is commingled with another formation: ☐ Yes ☒ No

Test Information:

Date: 10/14/2011 Hours: 24 Bbls oil: 10 Mcf Gas: 100 Bbls H2O: 0
Calculated 24 hour rate: Bbls oil: 10 Mcf Gas: 100 Bbls H2O: 0 GOR: 10000
Test Method: FLOWING Casing PSI: 2075 Tubing PSI: Choke Size: 12/64
Gas Disposition: SOLD Gas Type: WET BTU Gas: 1452 API Gravity Oil: 53
Tubing Size: 2 + 3/8 Tubing Setting Depth: 7503 Tbg setting date: 10/21/2011 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

Bridge Plug Depth: Sacks cement on top:

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Print Name: Cindy Vue

Title: Regulatory Analyst II Date: 10/31/2011 Email Cindy.Vue@anadarko.com

Attachment Check List

Att Doc Num	Name
400219502	FORM 5A SUBMITTED

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)