



**PO Box 884, Chanute, KS 66720**  
**620-431-9210 or 800-467-8676**

TICKET NUMBER 28148

LOCATION Dakota KS

FOREMAN F6224

## FIELD TICKET &amp; TREATMENT REPORT

## CEMENT

color

DATE		CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8.6.11		9160	Bobba State #3	20	10	55w	Lincoln
CUSTOMER Weirpiking-Tullerton				Limer			
MAILING ADDRESS				556			
				25			
CITY				Stg			
STATE		ZIP CODE		in			
JOB TYPE				Sut Saco			
HOLE SIZE				12 1/4			

JOB TYPE Surface HOLE SIZE 12 1/4 HOLE DEPTH 320' CASING SIZE & WEIGHT 8 5/8 24#  
 CASING DEPTH 319' DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT 15.2 SLURRY VOL 1.34 WATER gal/sk 6.5 CEMENT LEFT in CASING 20'  
 DISPLACEMENT \_\_\_\_\_ DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE \_\_\_\_\_

REMARKS: Safety meeting on Murrin #25. Rig up + circulate  
mix 260SKS Com 390cc 290gel. Drop plug and  
displace 19 BALS water. Cement did circulate  
Approx 5 BALS to pit

Thanks 20224

Cr 20 W

[illegible]

Ravin 3737

## AUTHORIZTION

**TITLE**

CO - 4-00

SALES TAX	
ESTIMATED	
TOTAL	

356.03

DATE 8/7/11

7855.56

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.





**CONSOLIDATED**  
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT**  
**CEMENT**

TICKET NUMBER 28196  
LOCATION Oakley, KS  
FOREMAN Walt Dinkel

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-24-11	9160	Bubba-State #3	20	10 <sup>3</sup>	55 <sup>00</sup>	Lincoln
CUSTOMER <u>Weirking - Fullerton Energy</u>			Limon			
MAILING ADDRESS			85 E. 5			
CITY	STATE	ZIP CODE	TRUCK #	DRIVER	TRUCK #	DRIVER
			399	Kelly Gable		
			460	Cory Davis		

JOB TYPE Production HOLE SIZE 7 7/8 HOLE DEPTH 7900' CASING SIZE & WEIGHT 5 1/2 - 17 #  
CASING DEPTH 7862' DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER P.C. - 4505'  
SLURRY WEIGHT 14 # SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING 23.16  
DISPLACEMENT 182.8 DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 6-7 BPM

REMARKS: Safety Meeting, Rig up on Murefin #25, ran Float Equipment  
Turbo-Cent, 1-3-5-7-9, 16-17-18, 21-23, Baskets on 2-79, Port Collar on 79  
Circ @ 100 Jts and on Bottom, mixed 10 SKs in R.H., 10 SKs in M.H.,  
Pump 500 gal Mud Flush, mixed 255 SKs class H, 10% salt, 5 # Kolseal, 2 # Col  
Clear Pump + Lines, release Plug + Displace 183 BBL H<sub>2</sub>O @ 1400 #  
max, Landed Plug @ 2000 #, release Pressure, Float Held

Thank You  
Walt - Kelly + crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401P	1	PUMP CHARGE	4,050 <sup>00</sup>	4,050 <sup>00</sup>
5406	100	MILEAGE	5 <sup>00</sup>	500 <sup>00</sup>
1115A	275 SKs	Class H Cement	22 <sup>00</sup>	6,050 <sup>00</sup>
1111	1308 #	Salt	.42	549 <sup>36</sup>
1110A	1375 #	Kolseal	.53	728 <sup>75</sup>
1118B	516 #	Bentonite	.24	123 <sup>84</sup>
1107	69 #	Fla-Seal	2 <sup>66</sup>	183 <sup>54</sup>
1144G	500 gal	Mud Flush	1 <sup>00</sup>	500 <sup>00</sup>
5407A	12.93	Ten Mileage Delivery	158	2,042 <sup>94</sup>
4159	1	AFU Float Shoe	413 <sup>00</sup>	413 <sup>00</sup>
4454	1	<del>Turbo Centralizers</del> Latch Down Plug	303 <sup>00</sup>	303 <sup>00</sup>
4136	10	Turbo-Centralizers	72 <sup>00</sup>	720 <sup>00</sup>
4130	3	Centralizers	58 <sup>00</sup>	174 <sup>00</sup>
4104	2	Baskets	276 <sup>00</sup>	552 <sup>00</sup>
4285	1	Port Collar	2,075 <sup>00</sup>	2,075 <sup>00</sup>
				18,968 <sup>43</sup>
		Less 15% Disc		2,844 <sup>81</sup>
				16,123 <sup>62</sup>
				820 <sup>29</sup>
			SALES TAX	
			ESTIMATED	
			TOTAL	16,940 <sup>91</sup>

Ravin 3737

AUTHORIZATION

*[Signature]*

TITLE Rig Supervisor

DATE 8/24/11

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.





ENTERED

TICKET NUMBER 28206  
LOCATION Oakley Ks  
FOREMAN Kelly Gable  
ORT Walt Dinkel  
Calo

## FIELD TICKET & TREATMENT REPORT CEMENT

DATE			CUSTOMER #		WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
9-2-11			9160		Bul-ha State #3	20	10 <sup>s</sup>	55W	Lincoln
CUSTOMER						TRUCK #			
Warping - Fullerton						DRIVER			
MAILING ADDRESS						TRUCK #			
						DRIVER			
						399 miles show			
						460 Cory Davis			
CITY									
STATE									
ZIP CODE									
HOLE DEPTH						CASING SIZE & WEIGHT			
						5 1/2 - 17 #			

JOB TYPE <u>Port Collar</u>	HOLE SIZE _____	HOLE DEPTH _____	CASING SIZE & WEIGHT <u>5 1/2 - 17 #</u>
CASING DEPTH _____	DRILL PIPE _____	TUBING <u>2 7/8 - 2586'</u>	OTHER <u>RC 4586'</u>
SLURRY WEIGHT <u>13.</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING _____
DISPLACEMENT <u>25 1/2</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE <u>5 BPM</u>
<div style="text-align: right;"> <u>Test Casing to 1500 #</u> </div>			

SLURRY WEIGHT 13 SLURRY VOL \_\_\_\_\_  
DISPLACEMENT 25 1/2 DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 5 Bpm  
REMARKS: Safety Meeting, rig up on Cadell Well Service, Test Casing to 1500#  
Held, open Tool, pump into, Home Circ,  
mixed 250 sls 60% open, 6% cal, 5# Kal seal, 1/4# Flo-Seal 2 1200# max  
Shut Tool, Test Casing to 1500# Held, ran 6-Jts, Circ Clean

Thank You  
Kelly + crew

[illegible]

Rayin 3737

**AUTHORIZTION**

**TITLE**

DATE \_\_\_\_\_

AUTHORIZATION [Signature] TITLE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.