



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600058

Date	9/8/11	Well Owner	Kerr McGee	Well No.	23-19	Lease	River Bend
County	Wich	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (Xtreme 14)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	1020		
Surface	8 5/8 CSG #24	Bottom of Surface		Fl.	1008		
Plug		Plug Landed @	990	Fl.	Time On	2200	
Production		Pipe Landed @	1008	Fl.	Plug Down	0500	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat	660	SKS		
Poz. Mix	202 TABS. Dr			
Calcium Chloride	80012090	2.5	%	
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	128	Miles		
Fuel Surcharge	128	miles		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	0410	0416
Disp. Rate	5 BPM	Mixing	0416	0445
Slurry Vol.	1.32 Cu. Ft./Sk	Change Valves	0445	0448
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0448	0500
Water/Cement	6.25 Gal/SK			
Water Temp.	60°F			
Total Slurry Vol.	155.1	BBLS Cement		
Landed Plug @	550	PSI/Final Lift @	275	PSI
Pre-Flush W/	30	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total
Displace W/	62.5	BBLS H <sub>2</sub> O	State CO 2.9%	Tax
Circulate	3	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		64			
1234		Bulk Truck		64			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim, Adam, Chris

Received By

Cody Sanders  
Customer or His Agent