

**FORM**  
**5**Rev  
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400220876

**DRILLING COMPLETION REPORT**

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 47120

4. Contact Name: Cindy Vue

2. Name of Operator: KERR-MCGEE OIL &amp; GAS ONSHORE LP

Phone: (720) 929-6832

3. Address: P O BOX 173779

Fax: (720) 929-7832

City: DENVER State: CO Zip: 80217-

5. API Number 05-123-32388-00

6. County: WELD

7. Well Name: MOSER

Well Number: 33-4

8. Location: QtrQtr: NESW Section: 4 Township: 2N Range: 65W Meridian: 6

Footage at surface: Distance: 2270 feet Direction: FSL Distance: 2423 feet Direction: FWL

As Drilled Latitude: 40.166753 As Drilled Longitude: -104.669512

## GPS Data:

Date of Measurement: 08/10/2011 PDOP Reading: 2.5 GPS Instrument Operator's Name: Renee Doiron

\*\* If directional footage at Top of Prod. Zone Dist.: 1315 feet. Direction: FSL Dist.: 47 feet. Direction: FWL

Sec: 4 Twp: 2N Rng: 65W

\*\* If directional footage at Bottom Hole Dist.: 1326 feet. Direction: FSL Dist.: 31 feet. Direction: FWL

Sec: 4 Twp: 2N Rng: 65W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 07/14/2011 13. Date TD: 07/16/2011 14. Date Casing Set or D&amp;A: 07/17/2011

## 15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 8430 TVD\*\* 7830 17 Plug Back Total Depth MD 8399 TVD\*\* 7799

18. Elevations GR 4859 KB 4874

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

## 19. List Electric Logs Run:

CBL  
NO OPEN HOLE LOGS, BRIDGED OUT @ 2220'

## 20. Casing, Liner and Cement:

**CASING**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24#	0	853	540	15	853	CALC
1ST	7+7/8	4+1/2	11.6#	0	8,421	227	6,710	8,421	CBL

**STAGE/TOP OUT/REMEDIAL CEMENT**

Cement work date: 07/17/2011					
Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	5,757	740	320	5,757
Details of work:					

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
NIOBRARA	7,567		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,824		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	8,264		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Cindy Vue

Title: Regulatory Analyst II Date: \_\_\_\_\_ Email: Cindy.Vue@anadarko.com

The subreport 'subreport3' could not be found at the specified location W:\Inetpub\Net\Reports\AttachListNew.rdlc. Please

#### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)