

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number: 400184678			
PluggingBond SuretyID 20030009			

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐

Refiling ☐
Sidetrack ☐

3. Name of Operator: NOBLE ENERGY INC 4. COGCC Operator Number: 100322
5. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202
6. Contact Name: MARI CLARK Phone: (303)228-4413 Fax: (303)228-4286
Email: mclark@nobleenergyinc.com
7. Well Name: NIX P Well Number: 28-69HN
8. Unit Name (if appl): _____ Unit Number: _____
9. Proposed Total Measured Depth: 10826

WELL LOCATION INFORMATION

10. QtrQtr: NWNE Sec: 28 Twp: 3N Rng: 67W Meridian: 6
Latitude: 40.202700 Longitude: -104.893010

Footage at Surface: 468 feet FNL 1987 feet FEL
FNL/FSL FEL/FWL

11. Field Name: WATTENBERG Field Number: 90750
12. Ground Elevation: 4794 13. County: WELD

14. GPS Data:

Date of Measurement: 05/25/2011 PDOP Reading: 1.1 Instrument Operator's Name: BRIAN BRINKMAN

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
78 FNL 1332 FEL 75 FNL 2105 FWL
Sec: 28 Twp: 3N Rng: 67W Sec: 27 Twp: 3N Rng: 67W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 452 ft

18. Distance to nearest property line: 468 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 680 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	407-87	320	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20030012

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

PLEASE SEE ATTACHED

25. Distance to Nearest Mineral Lease Line: 482 ft

26. Total Acres in Lease: 505

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	18+1/2	16+0/0		0	100	6	100	0
SURF	13+3/4	9+5/8	36	0	610	326	610	
1ST	8+3/4	7+0/0	26	0	7,391	854	7,391	
1ST LINER	6+1/8	4+1/2	11.6	7241	10,826		10,826	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments 1ST STRING TOP OF CEMENT = 200' ABOVE NIOBRARA. THE PRODUCTION LINER WILL BE HUNG OFF INSIDE 7" CASING. UNIT CONFIGURATION = 21: S/2SE/4, 22: S/2SW/4, 27: N2/NW/4, 28: N/2NE/4. NOBLE ENERGY INC. CERTIFIES THAT THE LEASES SHALL BE COMMITTED TO THE UNIT. WELL IS TO BE TWINNED WITH RALPH NIX PRODUCE P28-JI. AS DRILLED SUBMITTED.

34. Location ID: 331701

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: MARI CLARK

Title: REG. ANALYST II Date: 10/10/2011 Email: mclark@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nashin

Director of COGCC Date: 11/6/2011

API NUMBER

05 123 34658 00

Permit Number: _____ Expiration Date: 11/5/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us

2) Comply with Rule 317.i and provide cement coverage from end of 7" casing to a minimum of 200' above Niobrara. Verify coverage

with cement bond log.

3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
400184678	FORM 2 SUBMITTED
400212975	30 DAY NOTICE LETTER
400212976	DEVIATED DRILLING PLAN
400212977	LEGAL/LEASE DESCRIPTION
400212978	WELL LOCATION PLAT
400212981	PROPOSED SPACING UNIT

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed. No LGD or public comment received.	11/4/2011 2:10:18 PM
Permit	Okay to pass pending public comment 11/01/11.	10/17/2011 4:13:10 PM

Total: 2 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Material Handling and Spill Prevention	Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.
General Housekeeping	Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pickup trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.
Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) General Permit No. COR-038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location, and will remain in place until the pad reaches final reclamation.

Total: 3 comment(s)